


SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			LOCAL (NON-PARTICIPATING) 100% WILL COUNTY
				STP FUNDS			
				70% FEDERAL / 30% WILL COUNTY			
			0001	0008	0021		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2,100	2,100			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	453	453			
20101000	TEMPORARY FENCE	FOOT	981				981
* 20101200	TREE ROOT PRUNING	EACH	38				38
20200100	EARTH EXCAVATION	CU YD	38,430	38,430			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	46,920	46,920			
20400800	FURNISHED EXCAVATION	CU YD	18,600	18,600			
20800150	TRENCH BACKFILL	CU YD	1,026	1,007			19
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	14,240	14,240			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	14,290	14,290			
* 25000210	SEEDING, CLASS 2A	ACRE	3	3			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	400	344			56
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	400	344			56
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	400	344			56
* 25100115	MULCH, METHOD 2	ACRE	7	7			
25100630	EROSION CONTROL BLANKET	SQ YD	13,890	13,890			
* 25200110	SODDING, SALT TOLERANT	SQ YD	11,031	6,695			4,336
* 25200200	SUPPLEMENTAL WATERING	UNIT	46	46			
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	100	100			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	980	980			
28000400	PERIMETER EROSION BARRIER	FOOT	16,042	16,042			
28000500	INLET AND PIPE PROTECTION	EACH	3	3			
28000510	INLET FILTERS	EACH	111	111			
28100105	STONE RIPRAP, CLASS A3	SQ YD	136	136			
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,295	534	761		
28100207	STONE RIPRAP, CLASS A4	TON	954		954		
28200200	FILTER FABRIC	SQ YD	1,984	670	1,314		
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	22,220	22,220			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	38,164	30,493			7,671
35101400	AGGREGATE BASE COURSE, TYPE B	TON	921	921			
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	3,495	503			2,992
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	8,551	128			8,423
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	130	130			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	15,944	11,063			4,881
40600300	AGGREGATE (PRIME COAT)	TON	101	62			39

* DENOTES SPECIALTY ITEM

FILE NAME: D:\MCDON\2597281_35\A\Drawings\Contract-Spec\Roadway\Drawings\Summary\Summary.qxd

 100 S. WACKER DR. SUITE 500 CHICAGO IL 60606 TEL (312) 939-4000 FAX (312) 939-4198	USER NAME = jmoser.psh PLOT SCALE = 20.0000' / IN. PLOT DATE = 11/29/2012	DESIGNED - JRP DRAWN - MRF CHECKED - JRP DATE - 10/19/2012	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE. 1644	SECTION 01-00181-00-FP	COUNTY WILL	TOTAL SHEETS 328	SHEET NO. 3
	SCALE: NTS DRAWING NO. 1 OF 8 STA. TO STA.				ILLINOIS FED. AID PROJECT CONTRACT NO. 63647					