

**SUMMARY OF QUANTITIES**

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			LOCAL (NON-PARTICIPATING) 100% WILL COUNTY
				STP FUNDS			
				70% FEDERAL / 30% WILL COUNTY			
			0001	0008	0021		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	823	254			569
40600895	CONSTRUCTING TEST STRIP	EACH	5	5			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	167	115			52
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	17,667	14,476			3,191
40603335	HOT-MIX ASPHALT SURFACE COURSE, MX "D", N50	TON	1,415				1,415
40603340	HOT-MIX ASPHALT SURFACE COURSE, MX "D", N70	TON	5,565	3,439			2,126
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	128	128			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	31,459	4,520			26,939
42400800	DETECTABLE WARNINGS	SQ FT	540				540
44000100	PAVEMENT REMOVAL	SQ YD	7,099	5,512			1,587
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	19,612	6,063			13,549
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	178	178			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9,480	4,471			5,009
44000600	SIDEWALK REMOVAL	SQ FT	16,118	6,631			9,487
44003100	MEDIAN REMOVAL	SQ FT	3,006	2,501			505
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	200	60			140
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	200	60			140
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	300	100			200
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	300	100			200
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5,080	2,298			2,782
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	79	79			
50200300	COFFERDAM EXCAVATION	CU YD	30		30		
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1		
50300225	CONCRETE STRUCTURES	CU YD	415.5		415.5		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,156.5		1,156.5		
50300260	BRIDGE DECK GROOVING	SQ YD	2,071		2,071		
50300280	CONCRETE ENCASEMENT	CU YD	25		25		
50300300	PROTECTIVE COAT	SQ YD	3,629		3,629		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1		
50500505	STUD SHEAR CONNECTORS	EACH	12,560		12,560		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	339,270	8,000	331,270		
50800515	BAR SPLICERS	EACH	124		124		
* 50901720	BICYCLE RAILING	FOOT	1,136		1,136		
* 50901750	PARAPET RAILING	FOOT	690		690		
51201800	FURNISHING STEEL PILES HP14X73	FOOT	1,379		1,379		

\* DENOTES SPECIALTY ITEM

G:\v\000\1644\1644-00181-00-FP\Drawings\Contract\South Roadway\General\Summor\Summary\Summary.dgn  
 FILE NAME: G:\v\000\1644\1644-00181-00-FP\Drawings\Contract\South Roadway\General\Summor\Summary\Summary.dgn

**URS**  
 100 S. WACKER DR.  
 SUITE 500  
 CHICAGO, IL 60606  
 TEL (312) 939-1000  
 FAX (312) 939-4198

USER NAME: james\_ouen  
 FLOT SCALE: 20.0000 1/2 IN.  
 PLOT DATE: 11/24/2012

DESIGNED - JRP  
 DRAWN - MRF  
 CHECKED - JRP  
 DATE - 10/19/2012

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NTS      DRAWING NO. 2 OF 8      STA.      TO STA.

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1644	01-00181-00-FP	WILL	328	4
			CONTRACT NO. 63647	
ILLINOIS FED. AID PROJECT				