SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE: STP FUNDS, 70% FEDERAL / 30% WILL COUNTY 0001	0008	0021	LOCAL (NON-PARTICIPATING) 100% WILL COUNTY
51202305	DRIVING PILES	FOOT	1,379		1,379		
51203800	TEST PILE STEEL HP14X73	EACH	2		2		
51204650	PILE SHOES	EACH	45		45		
51500100	NAME PLATES	EACH	1		1		
51603000	DRILLED SHAFT IN SOIL	CU YD	42		42		
51604000	DRILLED SHAFT IN ROCK	CU YD	11		11		
52100520	ANCHOR BOLTS, 1"	EACH	40		40		
52100540	ANCHOR BOLTS, 1 1/2"	EACH	20		20		
54003000	CONCRETE BOX CULVERTS	CU YD	47	47			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4			
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	5	5			
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	405	395			10
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	251	251			
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	2				2
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	337	331			6
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	2,704	2,652			52
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	852	846			6
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	696	696			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	196	196			
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	18	18			
55100500	STORM SEWER REMOVAL 12"	FOOT	551	483			68
55100700	STORM SEWER REMOVAL 15"	FOOT	6				6
55101200	STORM SEWER REMOVAL 24"	FOOT	6				6
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	190		190		
60107700	PIPE UNDERDRAINS 6"	FOOT	4,334	4,334			
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	37	26			11
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1				1
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1			
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	1	1			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	19	19			

* DENOTES SPECIALTY ITEM

URS
100 S.WACKER DR.
SUITE 500
CHICAGO IL.60606
TEL (312)-939-1000
FAX (312)-939-4198

USER NAME = james_coush
PLOT SCALE = 20.0000 ' / IN.
PLOT DATE = 11/29/2012

DESIGNED - JRP
DRAWN - MRF
CHECKED - JRP
DATE - 10/19/2012

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS | DRAWING NO. 3 OF 8 | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1644	01-0018I-00-FP	WILL	328	5

CONTRACT NO. 63647

ILLINOIS FED. AID PROJECT

FILE NAME = U:\WEDOT_2012\38_70th\Drawings\Contract-South\Roadway\General\Summary_of_Quantities.dgn