SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE: STP FUNDS, 70% FEDERAL / 30% WILL COUNTY: 0001	0008	0021	LOCAL (NON-PARTICIPATING) 100% WILL COUNTY
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4			
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	26	25			1
60250200	CATCH BASINS TO BE ADJUSTED	EACH	3	3			
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1	1			
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3				3
60255500	MANHOLES TO BE ADJUSTED	EACH	9	6			3
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2			
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2			
60260100	INLETS TO BE ADJUSTED	EACH	4	2			2
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	2	2			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	6	3			3
60500050	REMOVING CATCH BASINS	EACH	6	6			
60500060	REMOVING INLETS	EACH	21	9			12
60602800	CONCRETE GUTTER, TYPE B	FOOT	89	89			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	7,463	4,717			2,746
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	7,993	5,376			2,617
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	3,708	3,708			
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	5,000	5,000			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	7,949	7,949			
60620800	CONCRETE MEDIAN, TYPE SB-9.12	SQ FT	1,141	1,141			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	250.0	250.0			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2			
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16			
67100100	MOBILIZATION	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	480	480			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	80	80			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,485	1,485			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	182	182			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	17,530	17,530			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	180	180			
* 70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	146	146			
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6,389	6,389			

* DENOTES SPECIALTY ITEM

URS
100 S.WACKER DR.
SUITE 500
CHICAGO IL 60606
TEL (312)-939-1000
FAX (312)-939-4198

USER NAME = jamesbush
PLOT SCALE = 20.0000 ' / IN.
PLOT DATE = 11/29/2012

DESIGNED - JRP
DRAWN - MRF
CHECKED - JRP
DATE - 10/19/2012

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS | DRAWING NO. 4 OF 8 | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1644	01-00181-00-FP	WILL	328	6

CONTRACT NO. 63647

ILLINOIS FED. AID PROJECT

FILE NAME = Q:\WICDOT_26367\001_MS4\Drawings\Contract-South\Roadway\Summary\C70Quantities.dgn