

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			LOCAL (NON-PARTICIPATING) 100% WILL COUNTY
				STP FUNDS			
				70% FEDERAL / 30% WILL COUNTY			
0001	0008	0021					
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	25				25
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	28				28
* 82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	2				2
* 83007400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. MAST ARM	EACH	10				10
* 83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	28				28
* 83600352	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8 5/8" X 6'	EACH	25				25
* 83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	61				61
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	31				31
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	29				29
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2				2
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2				2
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1	
* 86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1			1	
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1			1	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,306			1,306	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,906			1,906	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,424			2,424	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,598			1,598	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3,796			3,796	
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	37			37	
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	612			612	
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1			1	
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1			1	
* 87702980	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 50 FT.	EACH	2			2	
* 87703020	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 58 FT.	EACH	1			1	
* 87703030	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 60 FT.	EACH	1			1	
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16			16	
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4	
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	30			30	
* 87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	42			42	
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	5			5	
* 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2			2	
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1			1	
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	1			1	
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8			8	

* DENOTES SPECIALTY ITEM

FILE NAME = D:\KDCOH\20327281_0614\Drawings\Contract\Doc\Wishkey\Users\jpush\Drawings\Summary\Summary.dgn



USER NAME = james.push
 DESIGNED - JRP
 DRAWN - MRF
 CHECKED - JRP
 DATE - 10/19/2012
 PLOT SCALE = 28.0000 1/16"
 PLOT DATE = 11/29/2012

DESIGNED - JRP
 DRAWN - MRF
 CHECKED - JRP
 DATE - 10/19/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NTS DRAWING NO. 6 OF 8 STA. TO STA.

F.A.U. RTE. 1644	SECTION 01-00181-00-FP	COUNTY WILL	TOTAL SHEETS 328	SHEET NO. 8
CONTRACT NO. 63647				
ILLINOIS FED. AID PROJECT				