

GUARDRAIL

STATION - STATION	LOC	63000001 SPBGR TY A 6FT POSTS (FOOT)	63100167 TR BAR TRM T1 SPL TAN (EACH)	63100045 TRAF BAR TERM T2 (EACH)	63100070 TRAF BAR TERM T5 (EACH)	63100085 TRAF BAR TERM T6 (EACH)	63300705 RUB RAIL (FOOT)	78200410 GUARDRAIL MKR TYPE A (EACH)	78201000 TERMINAL MARKER - DA (EACH)
359+31.8 - 360+25.6	RT	0.0	1		1	1	93.8	2	1
359+97.6 - 360+49.8	LT	25.0		1	1			3	
363+68.1 - 364+45.3	RT	50.0		1	1		77.2	3	
363+92.4 - 366+61.2	LT	175.0	1			1		4	1
TOTALS		250.0	2	2	2	2	171	12	2

TEMPORARY PAVEMENT MARKING

STATION - STATION	TEMPORARY PAVEMENT MARKING					PAVEMENT MARKING TAPE, TYPE III	
	70300210	70300220	70300280	70300510	70300520	LETTERS AND SYMBOLS (SQ FT)	4"
	LETTERS AND SYMBOLS	LINE 4"	LINE 24"	LETTERS AND SYMBOLS	4"		
95TH ST., BEFORE STA. 307+20/308+15		0	0	0	146	4644	
307+20.0 - 333+37.3		0	12745	71	0	0	
372+42.8 - 386+34.0		182	4785	109	0	0	
KINGS RD., AFTER STA. 386+34		0	0	0	0	888	
55+83.7 - 67+63.4		0	0	0	0	857	
TOTALS:		182	17530	180	146	6389	

PAVEMENT MARKING

STA. TO STA.	THERMOPLASTIC PAVEMENT MARKING						POLYUREA PVMT MKG	PAVEMENT MARKERS	
	78000100	78000200	78000400	78000400	78000600	78000650	78008210	78100100	78100105
	LETTERS AND SYMBOLS (SQ FT)	LINE, 4" (FOOT)	LINE, 6" (FOOT)	LINE, 6" (SIDEWALK) (FOOT)	LINE, 12" (FOOT)	LINE, 24" (FOOT)	LINE, 4" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)
300+00.0 - 314+75.4	36	4086	472	99	202	66		74	
314+75.4 - 319+96.0	36	999	248	458	176	43		50	
319+96.0 - 333+37.3	73	4198	509	150	131	27		138	
333+37.3 - 372+42.8	73	9192	470		26	932		350	38
372+42.8 - 381+92.3	182	2033	985	200	194	91		98	
381+92.3 - 386+34.5	73	1544	471	394	86			30	
386+34.5 - 387+90.0	36	618							
55+83.7 - 60+34.9	36	96	235			38		15	
60+34.9 - 67+63.4	146	96	735	365	48			27	
TOTALS:	692	22863	4125	1666	789	339	932	782	38

SIGNING SCHEDULE

STATION	OFFSLT	SIGN DESCRIPTION	72000100	72400100	72400200	72400310	72400320	72400710	72400720	72800100	REMARKS
			SIGN PANEL T1 (SQ FT)	REMOV SIN PAN ASSY TA (EACH)	REMOV SIN PAN ASSY TB (EACH)	REMOV SIGN PANEL T1 (SQ FT)	REMOV SIGN PANEL T2 (SQ FT)	RELOC SIGN PANEL T1 (SQ FT)	RELOC SIGN PANEL T2 (SQ FT)	TELES STL SIN SUPPORT (FOOT)	
95TH STREET											
		ROAD CLOSED AHEAD w/35 MPH w/95th St.			1						
303+38	43.9	SPEED LIMIT 40	7.5								MOUNT TO EXISTING POST
303+38	44.0	NO PARKING	4.0								
312+09	5.5	LEFT TURN ONLY	7.5							14.5	
312+09	5.5	KEEP RIGHT	5.0								
312+36	39.6	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
314+35	38.0	STOP AHEAD				9.0					
315+30	2.0	KEEP RIGHT	5.0							14	
316+35	32.9	STOP AHEAD				9.0					
317+11	5.5	LEFT TURN ONLY	7.5							14.5	
317+11	5.5	KEEP RIGHT	5.0								
318+35	39.6	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
318+35	39.5	THRU TRAFFIC TURN				3.0					
319+42	36.8	STOP w/ALL WAY b/w STOP				1					
319+78	54.1	STOP				6.3		6.3		14	
319+78	54.1	ALL WAY				0.8					
320+20	50.0	STOP				6.3		6.3		14	
320+20	50.0	ALL WAY				0.8					
320+41	39.0	STOP w/ALL WAY b/w STOP				1					
322+30	32.9	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
323+57	2.0	LEFT TURN ONLY	7.5							14.5	
324+25	39.5	STOP AHEAD				9.0					
326+05	11.5	KEEP RIGHT				5.0		5.0			RELOCATE SIGN TO STA. 323+57, 2.0' RT.
328+27	39.8	35 MPH w/95th St.				1					
330+26	39.5	TEE INTERSECTION				7.5					
330+28	5.9	LEFT TURN ONLY	7.5							14.5	
330+28	5.9	KEEP RIGHT	5.0								
332+25	39.8	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
334+05		OBSTRUCTION MARKERS (6)				13.8					6 MARKER ASSEMBLIES AT 2.3 SQ. FT.
334+16	33.0	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
336+72	2.0	LEFT TURN ONLY	7.5							14.5	
336+72	2.0	KEEP RIGHT	5.0								
360+24	29.5	OBSTRUCTION MARKER (RIGHT)	3.0								COORDINATE LOCATIONS OF OBSTRUCTION MARKERS WITH BRIDGE PLANS
360+48	29.5	OBSTRUCTION MARKER (LEFT)	3.0								
363+70	29.5	OBSTRUCTION MARKER (LEFT)	3.0								
363+94	29.5	OBSTRUCTION MARKER (RIGHT)	3.0								
370+06	37.0	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
371+86	6.0	LEFT TURN ONLY	7.5							14.5	
371+86	6.0	KEEP RIGHT	5.0								
372+26	60.2	STOP				6.3		6.3		14	
372+26	60.2	3-WAY				0.8					
372+26	10.8	TWO DIRECTION LARGE ARROW				8.0					
372+60	59.6	STOP				6.3		6.3		14	
372+60	59.6	3-WAY				0.8					
372+90	25.7	STOP w/3-WAY				1					
373+00	6.0	LEFT TURN ONLY	7.5							14.5	
373+00	6.0	KEEP RIGHT	5.0								
374+13	4.3	LEFT LANE MUST TURN LEFT				6.3					
374+43	37.0	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
377+88	4.8	LEFT LANE MUST TURN LEFT				6.3					
378+52	38.9	ADV. INTERSECTION LANE CONTROL				10.0		10.0			MOUNT TO LIGHT POLE, STA. 384+60, LT.
379+30	26.9	SPEED LIMIT 30				7.5					
380+50	37.2	SPEED LIMIT 40	7.5								MOUNT TO LIGHT POLE
380+81	38.1	RIGHT LANE ENDS				6.3					
381+05	6.0	DUAL LEFT TURN ONLY	6.3							14.5	
381+05	6.0	KEEP RIGHT	5.0								
381+27	LEFT	LEFT ON GREEN ARROW ONLY	5.0								MOUNT ON NEW NE MAST ARM
381+29	RIGHT	LEFT ON GREEN ARROW ONLY	5.0								MOUNT TO NEW TS POST, NW CORNER
382+47	RIGHT	LEFT ON GREEN ARROW ONLY	5.0								MOUNT ON NEW SW MAST ARM
382+49	LEFT	LEFT ON GREEN ARROW ONLY	5.0								MOUNT TO NEW TS POST, SE CORNER
BOUGHTON RD											
59+70	5.0	LEFT TURN ONLY	7.5							14.5	
59+70	5.0	KEEP RIGHT	5.0								
61+27	6.7	KEEP RIGHT	5.0							14.5	
61+27	6.7	LEFT TURN ONLY	7.5								
63+65	37.4	RIGHT LANE ENDS w/300 FT AHEAD				1					
65+68	37.2	SPEED LIMIT 45				7.5		7.5			MOUNT TO LIGHT POLE, STA. 68+41, LT.
66+88	42.7	RIGHT TURN ONLY	7.5								MOUNT TO LIGHT POLE
TOTALS			235	2	4	127	10	38	10	215	

FILE NAME = c:\webdb\2012\3781_95th\drawings\contract\sheet\signing_schedule.dwg; g:\work\12\contract\mkg



100 S. WACKER DR.
SUITE 500
CHICAGO IL 60606
TEL (312) 939-1000
FAX (312) 939-4998

USER NAME = jamez.pugh
DESIGNED - JRP
DRAWN - MRF
CHECKED - JRP
DATE - 10/19/2012
REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SCALE: NTS DRAWING NO. 4 OF 4 STA. TO STA.

F.A.I. RTE. 1644 SECTION 01-00181-00-FP COUNTY WILL TOTAL SHEETS 328 SHEET NO. 21 CONTRACT NO. 63647 ILLINOIS FED. AID PROJECT