

## LIGHTING SUMMARY OF QUANTITIES

SP	PAY ITEM NO.	DESCRIPTION	UNIT	QUANTITY BREAKDOWN		TOTAL QUANTITY
				NAPERVILLE	BOLINGBROOK	
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	1	4
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1	0	1
	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	636	908	1544
	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	330	72	402
	81400100	HANDHOLE	EACH	2	0	2
	81603050	UNIT DUCT, 600V, 3-1C NO.6, 1/C NO.8 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	10760	3373	14133
	81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	0	4440	4440
	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	0	25	25
	82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	29	0	29
	82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	2	0	2
	83007400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. MAST ARM	EACH	0	10	10
	83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	29	0	29
	83600352	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8 5/8" X 6"	EACH	0	25	25
	83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	37	25	62
	84200804	REMOVAL OF POLE FOUNDATION	EACH	16	15	31
	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	14	15	29
	84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1	1	2
	84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1	1	2
	89502380	REMOVE EXISTING HANDHOLE	EACH	2	0	2
*	X8950077	REMOVE AND RELOCATE EXISTING LIGHTING CONTROLLER	EACH	1	1	2
*	X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	0	1	1
*	Z0033024	MAINTAIN EXISTING LIGHTING SYSTEM	L SUM	0.5	0.5	1
*	-	MAST ARM, ALUMINUM, STREET LIGHTING, 10 FT.	EACH	0	12	12
*	-	LIGHT POLE FOUNDATION, METAL, 11 1/2" BOLT CIRCLE, 8" X 7"	EACH	37	0	37

\* DESIGNATES SPECIAL PROVISIONS

I:\L\N\VE - 4\h\veddl\_20587281\_051\working\sectors\sectors\lighting\lighting.dwg, 2/1/2012, 4:11:23 PM

<b>URS</b> 100 S. WACKER DR. SUITE 500 CHICAGO, IL 60606 TEL 312-939-1000 FAX 312-939-4198	DESIGNED - MAE DRAWN - MAE CHECKED - DAD DATE - 2/1/2012	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		95TH STREET LIGHTING SUMMARY OF QUANTITIES		F.A.J. RTE. 1644	SECTION 01-00181-00-FP	COUNTY WILL	TOTAL SHEETS 328	SHEET NO. 130
	PLOT SCALE = 1/8" = 1'-0" PLOT DATE = 2/1/2012	SCALE: NONE DRAWING NO. 2 OF 30 STA. TO STA.		CONTRACT NO. 63647 ILLINOIS FED. AID PROJECT							