

95TH STREET (PROPOSED EXTENSION OF ROADWAY)

NO EXISTING LIGHTING IN THIS AREA

95TH STREET (PROPOSED EXTENSION)

MATCH LINE STA. 348+25

MATCH LINE STA. 362+75


**NOTES:**

1. THE CONTRACTOR SHALL NOT DE-ENERGIZE, DISCONNECT, OR REMOVE ANY EXISTING LIGHTING EQUIPMENT UNLESS A REPLACEMENT EQUIPMENT IS IN PLACE AND MADE OPERATIONAL BEFORE THE EXISTING EQUIPMENT CAN BE REMOVED.
2. NEW LOCATIONS OF ALL RELOCATED LIGHTING EQUIPMENT ARE SHOWN ON THE TEMPORARY AND PROPOSED LIGHTING PLANS.
3. INSTALL RELOCATED EXISTING LIGHTING CONTROLLER CABINETS ON NEW FOUNDATIONS. NEW FOUNDATIONS MUST MATCH EXISTING FOUNDATIONS IN SIZE AND CONDUIT LAYOUT. CONTRACTOR SHALL ALSO FURNISH AND INSTALL CONCRETE WORK PLATFORM IN FRONT OF NEW CONTROLLER CABINET PER THE STANDARDS AND DETAILS SHOWN ON THESE PLANS.

4. THE CONTRACTOR SHALL PROPERLY HANDLE AND DELIVER ALL REMOVED LIGHTING EQUIPMENT THAT WILL NOT BE REUSED TO THE OWNER'S PUBLIC WORKS DEPARTMENT DESIGNATED STORAGE/MAINTENANCE YARD. ALL COSTS RELATED TO REMOVAL, HANDLING, AND TRANSPORTATION OF THE REMOVED EQUIPMENT SHALL BE INCLUDED IN THE COST OF THE ITEM BEING REMOVED.

5. EXISTING WIRES AND CABLES THAT WILL NOT BE REUSED SHALL BE ABANDONED IN PLACE OR REMOVED BY THE CONTRACTOR AND DISPOSED OF OUTSIDE THE RIGHT OF WAY AT HIS OWN EXPENSE.

6. CONTRACTOR SHALL REMOVE THE EXISTING TWIN ARM MEDIAN LIGHT POLES SHOWN AND RELOCATE THE LIGHT POLE AND ONE MAST ARM AND A LUMINAIRE ON A NEW FOUNDATION IN THE NEW LOCATION SHOWN. THE REMAINING LIGHTING ARM AND LUMINAIRE SHALL BE REINSTALLED ON A NEW CONTRACTOR FURNISHED AND INSTALLED LIGHT POLE ON A NEW FOUNDATION AS SHOWN.



95TH STREET (PROPOSED EXTENSION)

95TH STREET (PROPOSED EXTENSION)

ALAN DEATHRAG DRIVE

EXISTING POLE TO REMAIN (TYP.)

EXISTING LIGHTING CONTROLLER "C" TO BE REMOVED AND RELOCATED. 100A, 240/480V, 1Ø, 3W VILLAGE OF BOLINGBROOK MAINTAINED STA. 373+08, 39' RT.

TWIN ARM LIGHT POLE TO BE REMOVED AND RELOCATED SEE NOTE 6 (TYP.)

**LEGEND**

- EXISTING LIGHTING UNIT TO REMAIN  
35' M.H., 10' M.A., 250W, 240V HPS LUMINAIRE  
VILLAGE OF BOLINGBROOK
- EXISTING LIGHTING UNIT TO BE REMOVED AND RELOCATED  
35' M.H., 10' M.A., 250W, 240V HPS LUMINAIRE  
VILLAGE OF BOLINGBROOK
- EXISTING LIGHTING CONTROLLER CABINET "C", TO BE REMOVED AND RELOCATED  
SINGLE DOOR, CONSOLE TYPE, 100A, 240/480V, 1Ø  
VILLAGE OF BOLINGBROOK MAINTAINED

FILE NAME: q:\vmp\2558738\15\h\o-ec\p\constr\p\roadway\lighting\sta-348-362.dgn



100 S. WACKER DR.  
SUITE 500  
CHICAGO, IL 60606  
TEL (312) 939-1000  
FAX (312) 939-4938

USER: NPM: jpmc@urscorp.com  
PLT: SCALE: 1"=50'  
PLT: DATE: 10/15/2012

DESIGNED - MAE  
DRAWN - MAE  
CHECKED - DAD  
DATE - 2/1/2012

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

95TH STREET  
EXISTING & REMOVAL LIGHTING PLAN (SHEET 3 OF 4)

SCALE: 1"=50' DRAWING NO. 9 OF 30 STA. 348+25 TO STA. 377+75

F.A.U. RTE. 1644	SECTION 01-00181-00-FP	COUNTY WILL	TOTAL SHEETS 328	SHEET NO. 137
ILLINOIS FED. AID PROJECT			CONTRACT NO. 63647	