



LEGEND

- EXISTING LIGHTING UNIT TO REMAIN
40' M.H., 12" M.A., 310W, 120V HPS LUMINAIRE
CITY OF NAPERVILLE
- EXISTING LIGHTING UNIT TO BE REMOVED AND RELOCATED
40' M.H., 12" M.A., 310W, 120V HPS LUMINAIRE
CITY OF NAPERVILLE
- EXISTING LIGHTING UNIT TO REMAIN DURING CONSTRUCTION
AND BE USED AS TEMPORARY LIGHT POLE
40' M.H., 12" M.A., 310W, 120V HPS LUMINAIRE
CITY OF NAPERVILLE
- EXISTING LIGHTING CONTROLLER CABINET,
SINGLE DOOR, CONSOLE TYPE, 100A, 120/240V, 1Ø
CITY OF NAPERVILLE MAINTAINED

PROPOSED LIGHT POLES
TO BE INSTALLED IN THIS
NEW SECTION OF ROADWAY
SEE SPECIAL NOTE
(TYP.)

PROPOSED LIGHT POLES
TO BE INSTALLED IN THIS
NEW SECTION OF ROADWAY
SEE SPECIAL NOTE
(TYP.)

SPECIAL NOTE:
NEW LIGHT POLES AND CONTROLLERS PROPOSED
IN THE NEW SECTION OF 95TH STREET DO NOT
NEED TO BE OPERATIONAL UNTIL THE ROADWAY
IS OPEN TO TRAFFIC.

NOTES:

1. THE CONTRACTOR SHALL MAINTAIN THE EXISTING LIGHTING EQUIPMENT IN A FULLY OPERATIONAL STATE ON THE TRAFFIC SIDE OF THE ROADWAY. THE CONTRACTOR SHALL REWIRE EXISTING LIGHTING CIRCUITS, AS NECESSARY, TO KEEP THE LIGHT POLES OPERATIONAL DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ANY EQUIPMENT, MATERIALS, AND LABOR NECESSARY TO ACCOMPLISH THIS GOAL INCLUDING TEMPORARY WIRING (UNDERGROUND OR AERIAL) OF POLES, LUMINAIRES AND LIGHTING CONTROLLERS.
2. ALL LIGHTING RELATED EQUIPMENT, MATERIALS AND LABOR FURNISHED AND INSTALLED BY THE CONTRACTOR DURING CONSTRUCTION TO MAINTAIN THE OPERATION OF THE EXISTING LIGHTING SYSTEM SHALL BE PAID FOR UNDER PAY ITEM "MAINTAIN EXISTING LIGHTING SYSTEM". THIS PAYMENT SHALL INCLUDE ALL MATERIALS AND EQUIPMENT NOT SPECIFICALLY SHOWN ON THE PLANS, BUT ARE NECESSARY TO MAINTAIN THE OPERATION OF THE LIGHTING SYSTEM DURING CONSTRUCTION.

URS
100 S. WACKER DR.
SUITE 500
CHICAGO IL 60606
TEL (312) 939-1000
FAX (312) 939-4988

USER NAME = jmae.pur
DESIGNED - MAE
DRAWN - MAE
CHECKED - DAD
DATE - 2/1/2012

REVISIONS
REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

95TH STREET
TEMPORARY LIGHTING PLAN - STAGE 1 (SHEET 2 OF 4)
SCALE: 1"=50' DRAWING NO. 12 OF 30 STA. 318+75 TO STA. 348+25

F.A.I.L. RTE. 1644	SECTION 01-00181-00-FP	COUNTY WILL	TOTAL SHEETS 328	SHEET NO. 140
CONTRACT NO. 63647				
ILLINOIS FED. AID PROJECT				

FILE NAME: c:\naper\01-2537381_5514\pave\pave\sect\sect_knack\95th\95th-1210.dgn