


EXISTING LIGHTING CONTROLLER "A"  
MUST REMAIN FULLY OPERATIONAL  
DURING CONSTRUCTION  
VILLAGE OF BOLINGBROOK MAINTAINED



IMPROVEMENT BEGINS  
STATION 55 + 83.71

IMPROVEMENT ENDS  
STATION 67 + 78.83

IMPROVEMENT ENDS  
STATION 386 + 34.49

**NOTES:**

- EXISTING LIGHT POLES LABELED WITH "ET" ARE LIGHT POLES THAT WILL BE REMOVED AND/OR RELOCATED IN A LATER STAGE.
- THE CONTRACTOR SHALL MAINTAIN THE EXISTING LIGHTING EQUIPMENT IN A FULLY OPERATIONAL STATE ON THE TRAFFIC SIDE OF THE ROADWAY. THE CONTRACTOR SHALL REWIRE EXISTING LIGHTING CIRCUITS, AS NECESSARY, TO KEEP THE LIGHT POLES OPERATIONAL DURING CONSTRUCTION. THE CONTRACTOR SHALL PROVIDE ANY EQUIPMENT, MATERIALS, AND LABOR NECESSARY TO ACCOMPLISH THIS GOAL INCLUDING TEMPORARY WIRING (UNDERGROUND AND AERIAL) OF POLES, LUMINAIRES AND LIGHTING CONTROLLERS.
- ALL TEMPORARY LIGHTING RELATED EQUIPMENT, MATERIALS AND LABOR FURNISHED AND INSTALLED BY THE CONTRACTOR DURING CONSTRUCTION TO MAINTAIN THE OPERATION OF THE EXISTING LIGHTING SYSTEM SHALL BE PAID FOR UNDER PAY ITEM "MAINTAIN EXISTING LIGHTING SYSTEM".
- FURNISH AND INSTALL AERIAL CABLES AND WOOD POLES TO SUPPORT CABLES IF PERMANENT UNDERGROUND WIRING CANNOT BE INSTALLED IN THIS STAGE OR EXISTING WIRING CANNOT BE MAINTAINED DURING CONSTRUCTION. NUMBER AND LOCATIONS OF TEMPORARY WOOD POLES AND AERIAL WIRING IS SHOWN AS AN EXAMPLE ONLY, AND ARE NOT LIMITED TO WHAT IS SHOWN ON THESE PLANS. PAYMENT FOR THIS WORK SHALL BE AS DESCRIBED IN NOTE 2 ABOVE.

**LEGEND**

- EXISTING LIGHTING UNIT TO REMAIN  
35' M.H., 10' M.A., 250W, 240V HPS LUMINAIRE  
VILLAGE OF BOLINGBROOK
- EXISTING LIGHTING UNIT TO BE REMOVED AND RELOCATED  
35' M.H., 10' M.A., 250W, 240V HPS LUMINAIRE  
VILLAGE OF BOLINGBROOK
- EXISTING LIGHTING UNIT TO REMAIN DURING CONSTRUCTION  
AND BE USED AS TEMPORARY LIGHT POLE  
35' M.H., 10' M.A., 250W, 240V HPS LUMINAIRE  
VILLAGE OF BOLINGBROOK
- NEW LOCATION OF EXISTING LIGHT POLES  
THAT ARE TO BE REMOVED AND RELOCATED  
VILLAGE OF BOLINGBROOK
- TEMPORARY TWIN ARM COMBINATION LIGHTING UNIT  
35' M.H., 2-10' M.A., 2-250W, 240V HPS LUMINAIRE  
INSTALLED ON TEMPORARY TRAFFIC SIGNAL WOOD POLE  
VILLAGE OF BOLINGBROOK

100 S. WACKER DR. SUITE 500 CHICAGO, IL 60606 TEL (312) 939-1000 FAX (312) 939-4198	DESIGNED - MAE DRAWN - MAE CHECKED - DAD DATE - 2/1/2012	REVISED - REVISED - REVISED - REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>		<b>95TH STREET TEMPORARY LIGHTING PLAN - STAGE 1 (SHEET 4 OF 4)</b>		F.A.L. RTE. 1644	SECTION 01-00181-00-FP	COUNTY WILL	TOTAL SHEETS 328	SHEET NO. 142	CONTRACT NO. 63647
	PLOT SCALE = 50.0000 1/2 IN. PLOT DATE = 08/16/2012	SCALE: 1"=50' DRAWING NO. 14 OF 30 STA. 377+75 TO STA. 386+34.49		ILLINOIS FED. AID PROJECT								