

SUMMARY OF QUANTITIES

Specialty items	Special Provision	Code No	Description	Unit	Construction Code Type 0005
		20200100	EARTH EXCAVATION	CU YD	393
		20800150	TRENCH BACKFILL	CU YD	12
*		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4800
*		25000400	NITROGEN FERTILIZER NUTRIENT	POUND	115
*		25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	115
*		25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	115
		25200110	SODDING, SALT TOLERANT	SQ YD	4800
		31101180	SUBBASE GRANULAR MATERIAL, TYPE B 2"	SQ YD	408
		31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	545
		40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	227
		40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10
		40600300	AGGREGATE (PRIME COAT)	TON	24
		40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2744
		40600895	CONSTRUCTING TEST STRIP	EACH	1
		40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	358
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2871
		42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	461
		42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	84
		42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	2263
		42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	1367
		42400800	DETECTABLE WARNINGS	SQ FT	160
		44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	4136
		44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	835
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9490
		44000600	SIDEWALK REMOVAL	SQ FT	1898
		44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	80
		44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	80
		44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	80
		44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	100
		44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	100
		50300300	PROTECTIVE COAT	SQ YD	6953
		60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1
		60250200	CATCH BASINS TO BE ADJUSTED	EACH	66

Specialty items	Special Provision	Code No	Description	Unit	Construction Code Type 0005
		60255500	MANHOLES TO BE ADJUSTED	EACH	33
		60260100	INLETS TO BE ADJUSTED	EACH	2
		60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5
	SP	60266600	VALVE BOXES TO BE ADJUSTED	EACH	6
		60600605	CONCRETE CURB, TYPE B	FOOT	196
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	553
		60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	8500
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	437
		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MC	5
		67100100	MOBILIZATION	L SUM	1
*		70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1
*		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
*		70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
		70106800	CHANGEABLE MESSAGE SIGN	CAL MC	10
		70300100	SHORT TERM PAVEMENT MARKING	FOOT	1361
		70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	578
		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	144
		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	241
		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1179
*		78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	782
*		78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24202
*		78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1833
*		78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1346
*		78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	241
*		78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	332
		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	332
*	SP	88600600	DETECTOR LOOP REPLACEMENT	FOOT	333
	SP	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1807
	SP	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	54
	SP	X8140115	HANDHOLE TO BE ADJUSTED	EACH	2
	SP	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	50
	SP	Z0070200	SURVEY MONUMENTS	EACH	2
		XX008744	STORM SEWERS, CLASS A, TYPE 1, 8"	FOOT	58

FILE NAME VILLAGE OF HODGKINS
EAST AVENUE
67TH ST. TO JOUET RD.
RESURFACING

USER NAME =
PLOT SCALE =
PLOT DATE =

DESIGNED -- THK
DRAWN -- JFP
CHECKED -- JLC
DATE -- 6/12

REVISED -- JLC 10-15-12
REVISED --
REVISED --
REVISED --

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

Frank Novotny & Associates, Inc.
Civil Engineers
Professional Consultants
185 Midway Drive • Wilmette, IL • 60091 • Telephone: (847) 937-8860 • Fax: (847) 937-8150
ILLINOIS PROFESSIONAL DESIGN PLAN NO. 139-P-0028

F.A.U. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2719	11-00019-00-RS	COOK	29	3

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT M-9003 (868)