

PLAN  
 DATE  
 BY  
 CHECKED  
 DATE  
 NO.

CODE NO.	PAY ITEM	UNIT	QUANTITY	SUMMARY OF QUANTITIES						
				ROADWAY#		LIGHTING#		TRAFFIC SIGNALS		NON-PARTICIPATING
				70% FED 30% LA	0004	70% FED 30% LA	0021	BUTTERFIELD RD &# COMMONWEALTH LN	INTERCONNECT#	EMERGENCY VEHICLE PREEMPTION
								0021	0021	0043
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	235	235						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	84	84						
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	38	38						
40600990	TEMPORARY RAMP	SO YD	142	142						
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,068	1,068						
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	566	566						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	355	355						
42001300	PROTECTIVE COAT	SO YD	2,986	2,986						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	710	710						
42400800	DETECTABLE WARNINGS	SO FT	96	96						
44000100	PAVEMENT REMOVAL	SO YD	331	331						
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	4,275	4,275						
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	244	244						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,060	2,060						
44000600	SIDEWALK REMOVAL	SO FT	691	691						
44003100	MEDIAN REMOVAL	SO FT	332	332						
44004250	PAVED SHOULDER REMOVAL	SO YD	1,902	1,902						
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SO YD	200	200						
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	500	500						
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	12,020	12,020						
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SO YD	23	23						
48203015	HOT-MIX ASPHALT SHOULDERS, 4 1/2"	SO YD	119	119						
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SO YD	1,221	1,221						
50105220	PIPE CULVERT REMOVAL	FOOT	21	21						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1						
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1						
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1						
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	612	612						
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	10	10						
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	52	52						
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	76	76						
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	199	199						
55100500	STORM SEWER REMOVAL 12"	FOOT	13	13						
56106400	ADJUSTING WATER MAIN 8"	FOOT	20	20						
56106600	ADJUSTING WATER MAIN 12"	FOOT	20	20						
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	2							2

\* STP (70% FED, 30% LA)  
 CMAQ (80% FED, 20% LA)  
 PER LOCAL AGENCY  
 AGREEMENT

\* SPECIAL PROVISION

+ CONSTRUCTION TYPE CODE = 0042    Δ SPECIALTY ITEMS



USER NAME = kaorenz	DESIGNED - TKS	REVISED -
FILE NAME = 01X0006-SHT-SumQty.dgn	DRAWN - TKS	REVISED -
PLOT SCALE = 98.000 / 1"	CHECKED - JMG	REVISED -
PLOT DATE = 12/4/2012	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

BUTTERFIELD ROAD AT COMMONWEALTH LANE  
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE    SHEET NO. 4 OF 108 SHEETS

F.A.I. RTE. 3545	SECTION 09-00170-00-CH	COUNTY DUPAGE	TOTAL SHEETS 108	SHEET NO. 4
FED. ROAD DIST. NO. 7 (ILLINOIS) FED. AID PROJECT				
CONTRACT NO. 63742				

FILE PATH = G:\CH08\0808\Road\PHASE 2\Sheets\01X0006-SHT-SumQty.dgn