

PLAN
 SUBMITTED BY DATE
 PLOTTED BY DATE
 NOTE BOOK NO. OF PAGES
 (1. OF 1 MAY CREATED)
 CARD FILE NAME

SUMMARY OF QUANTITIES				ROADWAY#	LIGHTING#	TRAFFIC SIGNALS			NON-PARTICIPATING
CODE NO.	PAY ITEM	UNIT	QUANTITY	70% FED 30% LA	70% FED 30% LA	BUTTERFIELD RD &# COMMONWEALTH LN	INTERCONNECT#	EMERGENCY VEHICLE PREEMPTION	100% ELMHURST
				0004	0021	70% FED 30% LA	70% FED 30% LA	100% ELMHURST	100% ELMHURST
							0021	0021	0043
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	530	530					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	550	550					
72000100	SIGN PANEL - TYPE 1	SQ FT	104	74		30			
72000200	SIGN PANEL - TYPE 2	SQ FT	55			55			
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	2	2					
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	17	17					
72400600	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	EACH	1	1					
72900100	METAL POST - TYPE A	FOOT	153	153					
72900200	METAL POST - TYPE B	FOOT	184	184					
Δ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146					
Δ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,075	2,075					
Δ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	909	909					
Δ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	101	101					
Δ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	530	530					
Δ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	88	88					
Δ 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	307	307					
Δ 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	4,428	4,428					
Δ 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	956	956					
Δ 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	325	325					
Δ 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	55	55					
Δ 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	59	59					
Δ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	66	66					
Δ 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2	2					
Δ 78200410	GUARDRAIL MARKERS, TYPE A	EACH	21	21					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	742	742					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	68	68					
Δ 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1		1				
Δ 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1				
Δ 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1			1			
Δ 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	1,105			705	400		
Δ 81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	84		10	74			
Δ 81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	717		600	117			
Δ 81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	395			395			
Δ 81400100	HANDHOLE	EACH	4			4			
Δ 81400200	HEAVY-DUTY HANDHOLE	EACH	5			5			
Δ 81400300	DOUBLE HANDHOLE	EACH	2			2			

* STP (70% FED, 30% LA)
 CMAQ (80% FED, 20% LA)
 PER LOCAL AGENCY
 AGREEMENT

* SPECIAL PROVISION

+ CONSTRUCTION TYPE CODE = 0042 Δ SPECIALTY ITEMS



USER NAME = ksloranz	DESIGNED - TKS	REVISED -
FILE NAME = D:\X008-SHT-SumQty.dgn	DRAWN - TKS	REVISED -
PLOT SCALE = 1/8" = 1' / in.	CHECKED - JMG	REVISED -
PLOT DATE = 12/4/2012	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

BUTTERFIELD ROAD AT COMMONWEALTH LANE
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 6 OF 108 SHEETS

F.A.U. RTE. 3545	SECTION 09-00170-00-CH	COUNTY DUPAGE	TOTAL SHEETS 108	SHEET NO. 6
CONTRACT NO. 63742				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

FILE PATH = E:\X008-SHT-SumQty.dgn