

PLAN SUBMITTED BY DATE
 NOTE BOOK NO. CHECKED BY
 FILE NAME

SUMMARY OF QUANTITIES				ROADWAY#	LIGHTING#	TRAFFIC SIGNALS			NON-PARTICIPATING
CODE NO.	PAY ITEM	UNIT	QUANTITY	70% FED 30% LA 0004	70% FED 30% LA 0021	BUTTERFIELD RD & COMMONWEALTH LN 70% FED 30% LA	INTERCONNECT# 70% FED 30% LA	EMERGENCY VEHICLE PREEMPTION 100% ELMHURST 0021	100% ELMHURST 0043
Δ • X8210005	TEMPORARY LUMINAIRE, HIGH PRESSURE SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4		4				
Δ • X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	1,304				1,304		
	Z0013798 CONSTRUCTION LAYOUT	L SUM	1	1					
	Z0018500 DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
	Z0000400 PERIMETER EROSION BARRIER	FOOT	4,146	4,146					
Δ • 70600240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	1	1					
	Z0030850 TEMPORARY INFORMATION SIGNING	SO FT	50	50					
Δ • Z0033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 2	EACH	1				1		
	Z0038117 PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1"	SO YD	2,768	2,768					
	Z0056608 STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	38	38					
	Z0056610 STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	139	139					
	Z0062456 TEMPORARY PAVEMENT	SO YD	900	900					
Δ • Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1			1			
+ • Z0076600	TRAINEES	HOOR	500	500					
+ • Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOOR	500	500					
	XY008812 RELOCATE LANDSCAPING STONE	SO FT	271	271					
Δ • X8570226	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1			1			
Δ • 81603100	UNIT DUCT, 600V, 4-1C NO.6, 1/C NO.10 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2,450		2,450				

STP (70% FED, 30% LA)
 CMAQ (80% FED, 20% LA)
 PER LOCAL AGENCY
 AGREEMENT

• SPECIAL PROVISION

+ CONSTRUCTION TYPE CODE = 0042 Δ SPECIALTY ITEMS



USER NAME = keironz	DESIGNED - TKS	REVISED -
FILE NAME = D:\2288-5HT_SumQty.dgn	DRAWN - TKS	REVISED -
PLOT SCALE = 50.000 / 1" = 50'	CHECKED - JMC	REVISED -
PLOT DATE = 12/4/2012	DATE - 10/22/2012	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

BUTTERFIELD ROAD AT COMMONWEALTH LANE
 SUMMARY OF QUANTITIES

SCALE: NOT TO SCALE SHEET NO. 9 OF 108 SHEETS

F.A.U. RTE. 3545	SECTION 09-00170-00-CH	COUNTY DUPAGE	TOTAL SHEETS 108	SHEET NO. 9
CONTRACT NO. 63742			FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT	

FILE PATH = G:\CH88\8888\Road\Phase 2\Sheet\A\11000008-541-SumQty.dgn