

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE 0005 TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	50
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	50
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	15
20200100	EARTH EXCAVATION	CU YD	300
20400800	FURNISHED EXCAVATION	CU YD	375
20800150	TRENCH BACKFILL	CU YD	10
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	3,500
25000110	SEEDING, CLASS 1A	ACRE	1.0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90
25100630	EROSION CONTROL BLANKET	SQ YD	3,500
28000400	PERIMETER EROSION BARRIER	FOOT	700
28000500	INLET AND PIPE PROTECTION	EACH	15
28100127	STONE RIPRAP, CLASS B4	SQ YD	50
28200200	FILTER FABRIC	SQ YD	50
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	1,325
35600700	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	SQ YD	1,325
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	670
40600300	AGGREGATE (PRIME COAT)	TON	13
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	40
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	990
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX 'D', N50	TON	1,000
44000100	PAVEMENT REMOVAL	SQ YD	670
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	420
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	225
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	225
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	225
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	225

CODE NO.	ITEM	UNIT	CONSTRUCTION TYPE CODE 0005 TOTAL QUANTITY
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	6,950
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	5,800
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	30
542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	30
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2
55100400	STORM SEWER REMOVAL 10"	FOOT	25
55100500	STORM SEWER REMOVAL 12"	FOOT	40
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1
60255500	MANHOLES TO BE ADJUSTED	EACH	4
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION 701501	L SUM	1
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	200
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,000
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	7
X2140100	GRADING AND SHAPING DITCHES, SPECIAL	FOOT	550
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6,100
X4811900	AGGREGATE SHOULDERS (SPECIAL)	TON	120
X6026050	SANITARY MANHOLES TO BE ADJUSTED	EACH	1
X7240505	RELOCATE SIGN PANEL AND POST	EACH	3
XX000610	RELOCATE EXISTING MAILBOX	EACH	7
XX004774	BRICK DRIVEWAY REMOVAL AND REPLACEMENT	SQ FT	900
Z0004510	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 3"	SQ YD	410
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52
XX008741	STORM SEWERS, CLASS B, TYPE 2 8"	FOOT	30
XX008742	INFILTRATION BASIN	SQ FT	1,000

* SPECIALTY ITEM