



DEMOLITION CONDITIONS LEGEND

- HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"
- DRIVEWAY PAVEMENT REMOVAL
- BRICK DRIVEWAY REMOVAL & REPLACEMENT (SPECIAL)
- EARTH EXCAVATION
- STORM STRUCTURE TO BE REMOVED
- TREE TO BE REMOVED
- STORM SEWER TO BE REMOVED
- PERIMETER EROSION BARRIER

DEMOLITION PLAN NOTES

1. ALL FIRE HYDRANTS SHOWN SHALL BE PROTECTED DURING CONSTRUCTION.
2. CONTRACTOR SHALL PROVIDE AND MAINTAIN POSITIVE DRAINAGE AWAY FROM THE PROPOSED AGGREGATE SUBGRADE DURING CONSTRUCTION. THIS WORK IS CONSIDERED INCLUDED IN THE COST OF THE CONTRACT.

FILE NAME = 8101-057 PR8.dwg	USER NAME = GW3	DESIGNED - DJG	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DEMOLITION PLAN			FA RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - GW3	REVISED -		SCALE: 1"=20'	SHEET NO. 8 OF 32 SHEETS	STA. 26+00 TO STA. 29+00	1254	12-00013-00-RS	LAKE	32	8
		CHECKED - DJG	REVISED -					CONTRACT # 63751				
		DATE - 08.10.2012	REVISED -		ILLINOIS FED. AID PROJECT M-4003(095)							