

CODE NO.	ITEM	UNIT	0011	0042	HBRP FUNDED	HANOVER PARK FUNDED
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8	0	8	0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	24	0	24	0
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	216	0	216	0
20400800	FURNISHED EXCAVATION	CU YD	290	0	290	0
20800150	TRENCH BACKFILL	CU YD	220	0	70	150
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	600	0	600	0
25000210	SEEDING, CLASS 2A	ACRE	0.13	0	0.13	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	11	0	11	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	11	0	11	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	11	0	11	0
25100630	EROSION CONTROL BLANKET	SQ YD	227	0	227	0
25200200	SUPPLEMENTAL WATERING	UNIT	2	0	2	0
28000400	PERIMETER EROSION BARRIER	FOOT	520	0	520	0
28000500	INLET AND PIPE PROTECTION	EACH	10	0	10	0
28100105	STONE RIPRAP, CLASS A3	SQ YD	48	0	48	0
28200200	FILTER FABRIC	SQ YD	48	0	48	0
31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	6	0	6	0
35101100	AGGREGATE BASE COURSE, TYPE A, 12"	SQ YD	570	0	570	0
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	73	0	73	0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	78	0	78	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	758	0	758	0
44000100	PAVEMENT REMOVAL	SQ YD	540	0	540	0
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	399	0	399	0
44000600	SIDEWALK REMOVAL	SQ FT	943	0	943	0
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	99	0	99	0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	40915	0	40915	0
50900200	STEEL RAILING, TYPE 2399 *	FOOT	27	0	27	0
51500100	NAME PLATES	EACH	1	0	1	0
54003000	CONCRETE BOX CULVERTS	CU YD	238	0	238	0
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	258	0	258	0
56100600	WATER MAIN 6" *	FOOT	45	0	0	45
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	4	0	4	0
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	0	1	0

CODE NO.	ITEM	UNIT	0011	0042	HBRP FUNDED	HANOVER PARK FUNDED
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	0	1	0
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	0	2	0
60255500	MANHOLES TO BE ADJUSTED	EACH	2	0	2	0
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	425	0	425	0
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A *	EACH	2	0	2	0
66400305	CHAIN LINK FENCE, 6' *	FOOT	70	0	70	0
67100100	MOBILIZATION	L SUM	1	0	1	0
70102640	TRAFFIC CONTROL AND PROTECTION, 701801	L SUM	1	0	1	0
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4" *	FOOT	60	0	60	0
78200410	GUARDRAIL MARKERS, TYPE A *	EACH	4	0	4	0
78201000	TERMINAL MARKER - DIRECT APPLIED *	EACH	2	0	2	0
X0322494	CURB CUT	FOOT	25	0	25	0
X0325318	LIGHTWEIGHT CELLULAR CONCRETE FILL	CU YD	91	0	91	0
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	20	0	20	0
X5010205	REMOVAL OF EXISTING STRUCTURE, SPECIAL	EACH	1	0	1	0
X5021510	COFFERDAMS (SPECIAL)	EACH	2	0	2	0
X6026055	SANITARY MANHOLE, SPECIAL *	EACH	1	0	0	1
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	84	0	84	0
Z0047500	PUMPING *	CAL DA	22	0	0	22
Z0057100	SANITARY SEWER 12" *	FOOT	70	0	0	70
Z0058000	SANITARY SEWER SPECIAL *	FOOT	34	0	0	34
Z0067700	STEEL CASINGS 20" *	FOOT	34	0	0	34
Z0076600	TRAINEES	HOUR	0	500	500	0
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	0	500	500	0
LR631020	TRAFFIC BARRIER TERMINAL, TYPE 1 *	EACH	2	0	2	0
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	362	0	362	0
X5610004	DUCTILE IRON WATER MAIN FITTINGS *	POUND	332	0	0	332
XX006119	TRAFFIC CONTROL AND PROTECTION (DETOUR)	L SUM	1	0	1	0
XX006947	HOT-MIX ASPHALT DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	36	0	36	0
XX008745	REMOVE AND REPAIR EXISTING GABIONS	CU YD	14	0	14	0
XX008746	VALVE WITH VALVE BOX, 6" *	EACH	1	0	0	1

* SPECIALITY ITEMS

Nov 09, 2012 - 9:33am \\pvt\mnt\cod\02841.DS\02841DS-03 - Sub.dwg

DATE	BY	DESCRIPTION
10-22-12	JR	REVISED PLANS PER COMMENTS FROM IDOT, HANOVER PARK, & NORTH COOK SWCD.
11-08-12	JR	REVISED PLANS PER COMMENTS FROM IDOT DATED 11-02-12.

DATE	BY	DESCRIPTION

PLOTTED BY:	AMT
CHECKED BY:	JR
DRAWN BY:	AMT
CHECKED BY:	JR
APPROVED BY:	DHT

PMA Engineers
Pavia-Marting & Co.
 910 W. Lake St.
 Roselle, IL 60172
 630-529-8000 fax: 630-834-6910
 Design Firm Professional Registration #184069336

TITLE: **LONGMEADOW LANE BOX CULVERT REPLACEMENT**
HANOVER PARK, IL
SUMMARY OF QUANTITIES

SCALE: NONE
 DATE: 8/6/2012
 JOB NO: 02841.DS
 SHEET 3 OF 20