

SUMMARY OF QUANTITIES

S.P.	CODE NO.	ITEM	UNIT	TOTAL 0021	TRAFFIC SIGNALS 0021	INTERCONNECT 0021
Δ	42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	717	717	
Δ	42400800	DETECTABLE WARNINGS	SQ FT	70	70	
Δ	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	87	87	
Δ	44000600	SIDEWALK REMOVAL	SQ FT	684	684	
Δ	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	87	87	
	67100100	MOBILIZATION	L SUM	1	1	
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
Δ	72000100	SIGN PANEL - TYPE 1	SQ FT	19.5	19.5	
Δ	78000600	THERMOPLASTIC PAYEMENT MARKING-LINE 12"	FOOT	755	755	
Δ	78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	162	162	
	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1	
	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	2359	724	1635
	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	86	86	
	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	135	135	
	81400100	HANDHOLE	EACH	6	4	2
	81400300	DOUBLE HANDHOLE	EACH	1	1	
	81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	235	235	
	82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	2	2	
	84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	1	1	
*	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1
	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1	
	86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1
	87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2185		2185
	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	385	385	
	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	735	735	
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1215	1215	
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1430	1430	
	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	150	150	
	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	375	375	

SUMMARY OF QUANTITIES

S.P.	CODE NO.	ITEM	UNIT	TOTAL 0021	TRAFFIC SIGNALS 0021	INTERCONNECT 0021
	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	1	1	
	87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1	1	
	87702830	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 20 FT.	EACH	2	2	
	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	8	
	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4	
*	87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	20	20	
	87900200	DRILL EXISTING HANDHOLE	EACH	1		1
	88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	4	
	88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1	
	88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1	
	88030310	SIGNAL HEAD, LED, 3-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1	
	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2	
	88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2	2	
	88200100	TRAFFIC SIGNAL BACKPLATE	EACH	4	4	
	88500100	INDUCTIVE LOOP DETECTOR	EACH	5	5	
	88600100	DETECTOR LOOP, TYPE I	FOOT	245	245	
	88700200	LIGHT DETECTOR	EACH	2	2	
	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1	1	
	88800100	PEDESTRIAN PUSH-BUTTON	EACH	4	4	
*	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
	89502200	MODIFY EXISTING CONTROLLER	EACH	1		1
*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1	
	89502380	REMOVE EXISTING HANDHOLE	EACH	3	3	
*	89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	1	1	
	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	4	4	
*	X8620200	UNINTERRUPTIBLE POWER SUPPLY, SPECIAL	EACH	1	1	
*	X8710024	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	2185		2185
*	X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	195	195	
*	20033046	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM-LEVEL 2	EACH	1		1
*	20033072	VIDEO VEHICLE DETECTION SYSTEM	EACH	1	1	

Δ INDICATES SPECIALTY ITEM