

SUMMARY OF QUANTITIES

CODE	PAY ITEM	UNIT	TOTAL QTY	CONSTRUCTION TYPE CODE	
				RESURFACING 0005 60% FEDERAL 40% LOCAL	RESURFACING 0043 100% LOCAL
* ~ 20800150	TRENCH BACKFILL	CU YD	35	0	35
21101615	TOPSOIL FURNISH & PLACE, 4"	SQ YD	550	550	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	10	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	10	10	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	10	0
25200100	SODDING	SQ YD	550	550	0
25200200	SUPPLEMENTAL WATERING	UNIT	10	10	0
40201000	AGGREGATE TEMPORARY ACCESS	TON	80	80	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	4,800	4,800	0
40600300	AGGREGATE (PRIME COAT)	TON	100	100	0
40800400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40	0
40600825	LEVELING BINDER (MACHINE METHOD), N50	TON	350	350	0
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD) N50	TON	990	990	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	500	500	0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N50	TON	2,700	2,700	0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	10	10	0
42101300	PROTECTIVE COAT	SQ YD	960	960	0
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	150	150	0
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	35	35	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	3,000	3,000	0
42400800	DETECTABLE WARNINGS	SQ FT	500	500	0
44000100	PAVEMENT REMOVAL	SQ YD	15	15	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	185	185	0
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	1,650	1,650	0
44000600	SIDEWALK REMOVAL	SQ FT	3,000	3,000	0
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1,700	1,700	0
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	10	10	0
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	130	130	0
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	80	80	0
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	500	500	0

* DENOTES SPECIALTY ITEM
 ~ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED



◆ Civil Engineers
 ◆ Municipal Consultants
 ◆ Established 1911

9933 Skewisville Road
 Westchester, Illinois 60154-4780
 Phone: 708/905-0980
 Fax: 708/905-1212

DESIGNED -- ---
 DRAWN -- LEV, DMM
 CHECKED -- ---
 DATE -- 10-18-12

REVISED --
 REVISED --
 REVISED --
 REVISED --

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. - FC STA. -

F.A.U. RTE. 2722	SECTION 12-00126-00-RS	COUNTY COOK	TOTAL SHEETS 26	SHEET NO. 4
CONTRACT NO. 63762			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(986)	