

**SUMMARY OF QUANTITIES**

CODE	PAY ITEM	UNIT	TOTAL QTY	CONSTRUCTION TYPE CODE	
				RESURFACING 0005	RESURFACING 0043
				60% FEDERAL 40% LOCAL	100% LOCAL
~ 60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	0
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	19	19	0
~ 60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	19	19	0
~ 60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	57	57	0
~ 60604100	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.12(MODIFIED)	FOOT	450	450	0
~ 60604700	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18(MODIFIED)	FOOT	1,200	1,200	0
67100100	MOBILIZATION	L SUM	1	1	0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2,000	2,000	0
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTER & SYMBOLS	SQ FT	240	240	0
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4	FOOT	13,000	13,000	0
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6	FOOT	1,900	1,900	0
* 78000500	THERMOPLASTIC PAVEMENT MARKING-LINE 8	FOOT	100	100	0
* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12	FOOT	640	640	0
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24	FOOT	400	400	0
*~ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	400	400	0
*~ XX006448	PVC COMBINED SEWER PIPE REPLACEMENT 10"	FOOT	18	0	18
*~ XX006451	10"X6" PVC SEWER SERVICE CONNECTIONS	EACH	1	0	1
~ X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	24,000	24,000	0
~ X6026624	VALVE BOXES TO BE ADJUSTED (SPECIAL)	EACH	1	1	0
~ X6020399	CONNECTION TO EXISTING MANHOLE	EACH	2	2	0
~ X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	55	55	0
~ X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1	0
~ Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	0
*~ Z0056800	SANITARY SEWER 6"	FOOT	30	0	30
*~ Z0057100	SANITARY SEWER 12"	FOOT	14	0	14

\* DENOTES SPECIALTY ITEM  
 ~ DENOTES THAT A SPECIAL PROVISION HAS BEEN PROVIDED

Drawing file: W:\Projects\12511152 - Maple Ave Resurfacing\WDEX.dwg Nov 16, 2012 4:49pm

**HANCOCK ENGINEERING**  
 Civil Engineers  
 Municipal Consultants  
 Established 1911

9923 Rivercrest Blvd  
 Westchester, Illinois 60154-2796  
 Phone: 708/665-0090  
 Fax: 708/665-1312

DESIGNED --	---	REVISED --	---
DRAWN --	LEV, DMM	REVISED --	---
CHECKED --	---	REVISED --	---
DATE --	10-18-12	REVISED --	---

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.D. RTE. 2722	SECTION 12-00126-00-RS	COUNTY COOK	TOTAL SHEETS 26	SHEET NO. 5
FED. ROAD DIST. NO. 1 ILLINOIS		CONTRACT NO. 63762 FED. AID PROJECT M-9003(986)		