

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0021	0031	0042	0044	0021			
				ROADWAY	SAFETY	LANDSCAPING	TRAINEES	OTHER	TRAFFIC SIGNALS			
									31ST STREET AT GOLFVIEW ROAD	IL ROUTE 171 AT COLEVIEW ROAD	INTERCONNECT	
Δ 81702100	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 12	FOOT	1800		1800							
Δ 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	2100		2100							
Δ 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	8150		8150							
Δ 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	15550		15550							
Δ 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	3600		3600							
Δ 81702160	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 1/0	FOOT	1000		1000							
Δ 81702230	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C 500MCM	FOOT	3000		3000							
Δ 81702441	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 2-12/C, 1-12/C GROUND	FOOT	600		600							
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	4		4							
84200804	REMOVAL OF POLE FOUNDATION	EACH	4		4							
Δ 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2	2								
Δ * 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2									2
Δ 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1						1			
Δ 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1								1	
Δ 87100140	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 12F	FOOT	1200		1200							
Δ 87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	3529									3529
Δ 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	394						394			
Δ 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1207						840		367	
Δ 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3673						1424		2249	
Δ 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	682						682			
Δ 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2830						1062		1768	
Δ 87301800	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 4 2C	FOOT	1411								1411	
Δ 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	154						154			
Δ * 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	2812						730		2082	
Δ 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	3								3	
Δ 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	2						2			

* REQUIRES SPECIAL PROVISION
Δ INDICATES SPECIALTY ITEM

FILE NAME = ... \82-Dum quant\2#63.S03.05.dgn	USER NAME = dte	DESIGNED - DTE	REVISED - Δ 1/3/13	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - DTE	REVISED -		SCALE: NONE	SHEET NO. 6 OF 11 SHEETS	STA.	TO STA.	3784	12-F3000-23-PK	COOK	133	9
		CHECKED - GAB	REVISED -						CONTRACT NO. 63764				
		DATE - 10/22/2012	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								