

CODED PAY ITEM NO.	ITEM	UNIT	TOTAL QUANTITY	0004	0021	0031	0042	0044	0021			
				ROADWAY	SAFETY	LANDSCAPING	TRAINEES	OTHER	TRAFFIC SIGNALS			
									31ST STREET AT GOLFVIEW ROAD	IL ROUTE 171 AT GOLFVIEW ROAD	INTERCONNECT	
Δ 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	2								2	
Δ 87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1								1	
Δ 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1							1		
Δ 87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1							1		
Δ 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1								1	
Δ 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1							1		
Δ 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	32							12	20	
Δ 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	8							4	4	
Δ <del>8780107</del>	CONCRETE FOUNDATION, (SPECIAL)	FOOT	80		80							
Δ 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	44							24	20	
Δ <del>87800415</del>	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13							13		
Δ 87900200	DRILL EXISTING HANDHOLE	EACH	2									2
Δ 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8							5	3	
Δ 88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3							1	2	
Δ 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1							1		
Δ 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2							2		
Δ 88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2							1	1	
Δ 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1							1		
Δ <del>8805150</del>	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2								2	
Δ 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2							2		
Δ <del>88055100</del>	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2								2	
Δ 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12							7	5	
Δ <del>88060110</del>	COMBINATION SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION OPTICALLY PROGRAMMED, 1-3 SECTION BRACKET MOUNTED	EACH	1								1	
Δ 88500100	INDUCTIVE LOOP DETECTOR	EACH	11							5	6	
Δ 88600100	DETECTOR LOOP, TYPE I	FOOT	955							577	378	
Δ 88700200	LIGHT DETECTOR	EACH	6							2	4	
Δ 88700300	LIGHT DETECTOR AMPLIFIER	EACH	2							1	1	
Δ 88800100	PEDESTRIAN PUSH-BUTTON	EACH	2							2		
Δ 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2							1	1	
Δ 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4479		2000							2479

\* REQUIRES SPECIAL PROVISION  
Δ INDICATES SPECIALTY ITEM