

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	G-11R	KENDALL	514	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY	URBAN												
				ROADWAY	ORCHARD / MINKLER TRAFFIC SIGNALS	DOUGLAS STREET TRAFFIC SIGNALS	FOREST AVENUE TRAFFIC SIGNALS	WASHINGTON / PLAINFIELD TRAFFIC SIGNALS	GROVE / PLAINFIELD TRAFFIC SIGNALS	SCHOOL ENTRANCE TRAFFIC SIGNALS	HIGHWAY LIGHTING	HIGHWAY LIGHTING GROVE ROAD	EMERGENCY VEHICLE PREEMPTION	SIDEWALK & BIKE PATH	QUARRY ENTRANCE	UTILITIES
				FEDERAL = 80% STATE = 20%	FEDERAL = 80% STATE = 10% COUNTY = 5% VILLAGE = 5%	FEDERAL = 80% STATE = 13.4% COUNTY = 0% VILLAGE = 6.6%	FEDERAL = 80% STATE = 10% COUNTY = 0% VILLAGE = 10%	FEDERAL = 80% STATE = 0% COUNTY = 10% VILLAGE = 10%	VILLAGE = 100%	VILLAGE = 100%	COUNTY = 50% VILLAGE = 50%	VILLAGE - 100%	FEDERAL = 80% VILLAGE = 20%	VILLAGE = 100%	VILLAGE = 100%	
				0003	01	02	0021	03	04	07/26/12	0021	0021	0028	0003	0043	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	676	676												
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1516	1516												
20101000	TEMPORARY FENCE	FOOT	1312	1312												
20101100	TREE TRUNK PROTECTION	EACH	8	8												
20200100	EARTH EXCAVATION	CU YD	79520	79520												
* 20200200	ROCK EXCAVATION	CU YD	362	362												
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5614	5614												
20400800	FURNISHED EXCAVATION	CU YD	6510	6510												
20800150	TRENCH BACKFILL	CU YD	9395	9395												
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	16470	16470												
25000200	SEEDING, CLASS 2	ACRE	6	6												
25000300	SEEDING, CLASS 3	ACRE	2	2												
25000350	SEEDING, CLASS 7	ACRE	11	11												
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1082	1082												
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1082	1082												
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1082	1082												
25100105	MULCH, METHOD 1	ACRE	11	11												
25100115	MULCH, METHOD 2	ACRE	18	18												
25100630	EROSION CONTROL BLANKET	SQ YD	4860	4860												
25100900	TURF REINFORCEMENT MAT	SQ YD	775	775												
25200110	SODDING, SALT TOLERANT	SQ YD	49885	49885												
25200200	SUPPLEMENTAL WATERING	UNIT	2200	2200												
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	270	270												
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	14900	14900												
28000305	TEMPORARY DITCH CHECKS	FOOT	785	785												
28000400	PERIMETER EROSION BARRIER	FOOT	20100	20100												
28000500	INLET AND PIPE PROTECTION	EACH	430	430												
28001000	AGGREGATE (EROSION CONTROL)	TON	330	330												
28100103	STONE RIPRAP, CLASS A2	SQ YD	70	70												
28100105	STONE RIPRAP, CLASS A3	SQ YD	210	210												

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE: 7/18/2012 DRAWN BY: SJF CHECKED BY: MED

TUB PROJ: 6306013
 PLOT DATE: 7/18/2012
 FILE NAME: P:\CIVIL\DOT_DIST3\0vego\Phase II\SUMMARY_OF_QUANTITY.dgn