CONTRACT NO. 66420

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-)R	KENDALL	514	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	UNIT	TOTAL QUANTITY (URBAN)	ROADWAY	ORCHARD / MINKLER TRAFFIC SIGNALS	DOUGLAS STREET TRAFFIC SIGNALS	FOREST AVENUE TRAFFIC SIGNALS	WASHINGTON / PLAINFIELD TRAFFIC SIGNALS	GROVE / PLAINFIELD TRAFFIC SIGNALS	SCHOOL ENTRANCE TRAFFIC SIGNALS	HIGHWAY LIGHTING	HIGHWAY LIGHTING GROVE ROAD	EMERGENCY VEHICLE PREEMPTION	SIDEWALK & BIKE PATH	QUARRY ENTRANCE	UTILITIES
				FEDERAL = 80% STATE = 20%	FEDERAL = 80% STATE = 10% COUNTY = 5% VILLAGE = 5%	FEDERAL = 80% STATE = 13.4% COUNTY = 0% VILLAGE = 6.6%	FEDERAL = 80% STATE = 10% COUNTY = 0% VILLAGE = 10%		FEDERAL = 80% STATE = 0% COUNTY = 10% VILLAGE = 10%	VILLAGE = 100%	VILLAGE = 100%	COUNTY = 50% VILLAGE = 50%	VILLAGE - 100%	FEDERAL = 80% VILLAGE = 20%	VILLAGE = 100%	VILLAGE = 100%
				0003	0021						0021		0021	0028	0003	0043
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	323	323												
48100100	AGGREGATE SHOULDERS, TYPE A	TON	1688	1688												
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	583	583												
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	166	166												
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1021	1021												
50104400	CONCRETE HEADWALL REMOVAL	EACH	13	13												
50105220	PIPE CULVERT REMOVAL	FOOT	2248	2248												
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2896	2896												
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	98	98												
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	68	68												
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	76	76												
542A1093	PIPE CULVERTS, CLASS A, TYPE 2 48"	FOOT	101	101												
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	28	28												
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	20	20												
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	140	140												
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4												
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	9	9												
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4												
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	4	4												
54213672	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 27"	EACH	2	2												
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2												
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1												
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1	1												
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	2	2												
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	2	2												
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	6155	6155												
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	1159	1159												
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	956	956												
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	475	475												
550A0130	STORM SEWERS, CLASS A, TYPE 1 27"	FOOT	13	13												

* DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE 7/18/2012
DRAWN BY SJF
CHECKED BY MED

TUS PROJ. #3UR6014
PLOT DATE = 7/18/2012
FILE NAME = P:\Civil_IDOT_DIST3\Drawings\Phase II\SUMMARY_OF_QUANTITY.dgn