

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	Q-1R	KENDALL	514	34
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVING SCHEDULE

STA. TO STA.	PCC PAVEMENT 9 3/4" (JOINTED) (SQ. YD.)	PCC PAVEMENT 9 1/4" (JOINTED) (SQ. YD.)	PCC PAVEMENT 8 1/4" (JOINTED) (SQ. YD.)	PCC PAVEMENT 8" (JOINTED) (SQ. YD.)	PCC PAVEMENT 7 3/4" (JOINTED) (SQ. YD.)	PROTECTIVE COAT (SQ. YD.)	SUBBASE GRANULAR MATERIAL, TYPE A 12" (SQ. YD.)	AGGREGATE SUBGRADE IMPROVEMENT 24" (SQ. YD.)	AGGREGATE BASE COURSE, TYPE A, 8" (SQ. YD.)	BITUMINOUS MATERIALS (PRIME COAT) (GAL)	INCIDENTAL HOT MIX ASPHALT SURFACING (TON)	HOT-MIX ASPHALT SHOULDERS, 8" (SQ. YD.)	AGGREGATE SHOULDERS TYPE B, 6" (SQ. YD.)
IL ROUTE 71													
774+00 TO 780+45													568.1
780+45 TO 787+00	2,596.1					2,596.1	2,985.0			376.4		1,003.6	
787+00 TO 801+00	10,352.5					10,352.5	12,819.4						
801+00 TO 816+00	10,063.5					10,063.5	11,706.2						
816+00 TO 831+00	8,884.8					8,884.8	6,538.8	5,344.4					
831+00 TO 846+00 (INCLUDES PARADISE)	10,109.1					10,109.1	12,595.4						
846+00 TO 858+00	7,757.5					7,757.5	8,987.0						
858+00 TO 873+00	9,103.4					9,103.4	3,837.7	7,777.8					
873+00 TO 888+00 (INCLUDES CULUMET S	11,137.8					11,137.8	13,662.3						
888+00 TO 903+00	10,460.4					10,460.4	8,989.5	2,977.8					
903+00 TO 918+00	10,940.4					10,940.4	12,576.5						
918+00 TO 918+59.01	575.8					575.8	663.1						
ORCHARD / MINKLER ROAD													
56+70 TO 65+00				5,307.5		5,307.5	5,730.3						
65+00 TO 71+30	4,168.5					4,168.5	5,330.6						
MAIN STREET CUL-DE-SAC													
									414.2	402.9	121.2		
DOUGLAS STREET (MAIN STREET)													
				2,681.6		2,681.6	2,668.7						
FOREST AVENUE													
46+86.01 TO 49+67					1,339.7	1,339.7	1,490.4						
50+33.01 TO 51+59.85					814.4	814.4	860.9						
PLAINFIELD ROAD/WASHINGTON STREET													
189+00 TO 199+61		8,533.3				8,533.3	9,593.8						
200+39 TO 207+00			4,456.1			4,456.1	4,848.5						
FRANKLIN STREET													
			666.2			666.2	718.3			6.6		17.7	14.7
PROJECT TOTAL	96149.8	8533.3	5122.3	7989.1	2154.1	119948.6	126602.4	16100.0	414.2	785.9	121.2	1021.3	582.8

NOTE: SEE ENTRANCE SCHEDULE AND JOINT USE PATH SCHEDULE FOR ADDITIONAL PAVING QUANTITIES.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. _____
 HORIZ. _____
 DATE: 7/5/2012

DRAWN BY: SJF
 CHECKED BY: MED

TUC PROJ: 1305914
 PLOT DATE: 7/5/2012
 FILE NAME: p:\civil\1305914\1305914.dgn