

F.A.P. RTE. 311	SECTION 11-11R	COUNTY KENDALL	TOTAL SHEETS 514	SHEET NO. 40
STA. 10 STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

**GUARDRAIL SCHEDULE**

STATION	TO STATION	OFFSET	REMOVE AND REERECT	REMOVE & REERECT	TRAFFIC BARRIER	TRAFFIC BARRIER	TRAFFIC BARRIER	TRAFFIC BARRIER	TRAFFIC BARRIER	COMMENTS
			STEEL PLATE BEAM	TRAFFIC BARRIER	TRAFFIC BARRIER		TRAFFIC BARRIER	TRAFFIC BARRIER	TRAFFIC BARRIER	
			GUARDRAIL	TERMINAL TYPE 1 SPECIAL	SPECIAL (FLARED)	TERMINAL TYPE 6	DIRECT APPLIED	REMOVAL	REMOVAL	
			LENGTH (FEET)	EACH	EACH	EACH	EACH	LENGTH (FEET)	LENGTH (FEET)	
MINKLER RD./ORCHARD RD.										
55+00.0	61+33	RT	633.0							
61+33.0	61+58	RT		1				1		
67+80.9	68+30.9	RT			1			1	50	
68+30.9	71+46.3	RT	315.4							
71+46.3	71+61.0	RT					1		14.7	
68+67.2	69+17.2	LT			1			1	50	
69+17.2	71+46.3	LT	229.1							
71+46.3	71+61.0	LT					1		14.7	
TOTAL			1178	1	2	2	3		129.4	

**CLASS D PATCHES, 10"**

STATION	TYPE 1	TYPE II	TYPE III	TYPE IV	COMMENTS	
						AREA (SQ YD)
786+41			15.0			
798+85				69.3		
822+03	RT	6.1				
825+63	RT	6.3				
828+76	RT	7.6				
837+27			17.4			
839+17	RT	8.0				
843+76	RT	9.3				
847+85				28.5		
852+50	RT	5.8				
854+01	RT	6.3				
862+37			22.1			
864+09				35.2		
866+90	RT		20.0			
868+59	RT	5.0				
870+30	RT	4.9				
872+00	RT	5.0				
873+70	RT	4.7				
875+41	RT	4.2				
877+11	RT	6.6				
878+53	RT	4.3				
882+11	RT	6.8				
883+33	RT	6.1				
884+83	RT	6.3				
886+33	RT	6.5				
887+83	RT	6.9				
889+33	RT	6.7				
890+83	RT	7.1				
892+32	RT	7.9				
893+49	RT	8.9				
894+98	RT	13.8				
896+50	RT	14.7				
897+70	RT		15.4			
898+97	RT	8.9				
900+47	RT	8.9				
901+97	RT	8.9				
903+48	RT	8.9				
59+61				27.3	MINKLER	
50+46				86.5	FOREST	
159+00				40.8	PLAINFIELD	
19+63				55.1	H.S. ENTRANCE	
TOTALS		18.1	193.3	89.9	322.7	

**CONTROLLED LOW STRENGTH MATERIAL**

STATION	OFFSET	VOLUME (CU. YD.)
818+07	AR.	53.3
837+00	AR.	29.08
856+17	AR.	163.63
TOTAL		246.0

**HMA SURFACE REMOVAL, 1 1/2"**

STATION	TO STATION	AREA (SQ. YD.)
MAIN ST		
51+31.08	54+18.60	706.0
TOTAL		706.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES**

SCALE: VERT.  
HORIZ.  
DATE 7/5/2012

DRAWN BY RLH  
CHECKED BY WED

T:\S PROJ\130528\A  
PLOT DATE = 7/5/2012  
FILE NAME = p:\civil\1\dot\_data\3\anawgo\phase\_11\Schedule.dgn