CONTRACT NO. 66420

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1)R	KENDALL	514	42
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

PIPE RUN	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	LENGTH	SLOPE	STORM SEWERS, CLASS A, TYPE 1														STORM SEWERS, CLASS A, TYPE 2																S.S. CLASS A, TYPE 3	STORM SEWER (WATER MAIN REQUIREMENTS)						TRENCH BACKFILL
			FEET	%	12"	12" R.G	15"	15" R.G	18"	24"	24" R.G	27"	30"	30"EQRS	36"	42"	42" R.G	54"	12"	12" R.G	15"	15" R.G	18"	18" R.G	24"	24" R.G	27"	30"	30" R.G	36"	36" R.G	42"	42" R.G	54"	48"	12"	15"	24"	30"	36"	42"	CU YD
100	1B-01-FES	1B-02-MHA5	256.4	0.25					256.4																																	6.8
101	1B-04-INA	1B-05A-MHA4	26.9	0.56	26.9																																					1.8
102	1B-03-IN A	1B-02-MHA5	7.8	1.28	7.8																																					0.1
103	1B-02-MHA5	1B-06-CS5	30.1	0.33						30.1																																0
104	1B-05-FES	1B-05A-MHA4	3.9	0.00					3.9																																	0
105	1B-05A-MHA4	1B-06-CS5	67.8	0.00					67.8																																	6.4
106	1B-06-CS5	1B-07-FES	2.1	0.00						2.1																																0
107	1B-08-MHA4	1B-06-CS5	132.9	0.32					132.9																																	0
108	1B-10-INA	1B-09-IN B	63.4	0.47	63.4																																					6.9
109	1B-09-IN B	1B-08-MHA4	4.6	2.17	4.6																																					0
110	1B-11-MHA4	1B-08-MHA4	234.6	0.31	234.6																																					10.6
111	1B-12-INA	1B-11-MHA4	6.5	1.54	6.5																																					0
112	3-01-INA	3-02-MHA4	5.1	1.96	5.1																																					0.2
113	3-02-MHA4	3-03-MHA4	174.7	0.49	174.7																																					0
114	3-04-INA	3-03-MHA4	5.7	1.75	5.7																																					0.2
115	3-03-MHA4	3-10-MHA5	158.5	0.47																	158.5																					0
116	3-10A-FES	3-10-MHA5	12.5	3.20								12.5																														0
117	3-09-INA	3-10-MHA5	5.7	1.75															5.7																							0.5
118	3-10-MHA5	3-11B-MHA5	157	0.33																							157															0
119	3-11-INA	3-11B-MHA5	9.6	2.08	9.6																																					0.2
120	3-11B-MHA5	3-13-MHA5	160.8	0.37																							160.8															0
121	3-13-MHA5	3-14-MHA5	10.5	0.29																							10.5															0
122	3-14-MHA5	3-15-MHA5	82	0.16																							82															106.4
123	3-15-MHA5	3-15A-MHA5	4.9	6.94																							4.9															0
124	3-05-INA	3-06-MHA4	8.3	1.20	8.3																																					0.2
125	3-06-MHA4	3-07-MHA4	74.9	2.28	74.9																																					0
126	3-08-INA	3-07-MHA4	8.5	2.35															8.5																							0.5
127	3-07-MHA4	3-12-MHA5	164.8	0.32																	164.8																					33.8
128	3-11A-INA	3-12-MHA5	8.5	1.18															8.5																							0
129	3-12-MHA5	3-15A-MHA5	160.6	0.26																			160.6																			0
130	3-15A-MHA5	3-16-MHA5	165.8	0.60																							165.8															0
131	3-16-MHA5	3-17-MHA5	77.6	0.76																							77.6															0
132	3-17-MHA5	3-19-MHA5	161.4	0.69																							161.4															0
133	3-18-INA	3-19-MHA5	5.2	1.92	5.2																																					0.2
134	3-19-MHA5	3-20-MHA5	222.4	0.72																							222.4															144.6
135	3-22-INA	3-21-INB	44.7	0.56															44.7																							8.6
136	3-21-INB	3-20-MHA5	3.1	3.23	3.1																																					0
137	3-20-MHA5	3-23-FES	139.3	0.74																							139.3															0
138	3-24-INA	3-25-INB	27.5	4.47	27.5																																					2
139	3-25-INB	3-26-FES	13.3	1.88	13.3																																					0
140	4-01-INA	4-02B-MHA5	83.3	0.50	83.3																																					5.7
141	4-02-INA	4-02A-FES	15.8	2.28	15.8																																					0.2
142	4-03-INA	4-03A-MHA4	6	1.67	6																																					0.3
143	4-01A-FES	4-02B-MHA5	5.5	0.55										5.5																												0
144	4-02B-MHA5	4-03B-FES	116.4	0.17										116.4																												26.7
145	4-03A-MHA4	4-02B-MHA5	39.2	0.41					39.2																																	0
		TOTAL THIS SHEET			776.3	0	0	0	500.2	32.2	0	12.5	0	121.9	0	0	0	0	67.4	0	323.3	0	160.6	0	0	0	1181.7	0	0	0	0	0	0	0	0	0	0	0	0	0	0	362.9

LEGEND

R.G. = RUBBER GASKETED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE 7/5/2012

DRAWN BY SJF

CHECKED BY MED

TUG PROJ.-319264
PLOT DATE = 7/5/2012
FILE NAME = pw:\\\\dot_dist3\\oa=wgo\phase I\Schedule*.dgn