CONTRACT NO. 66420

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-)R	KENDALL	514	43
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

PIPE RUN	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	LENGTH	SLOPE	STORM SEWERS, CLASS A, TYPE 1														STORM SEWERS, CLASS A, TYPE 2																S.S. CLASS A, TYPE 3	STORM SEWER (WATER MAIN REQUIREMENTS)						TRENCH BACKFILL
			FEET	%	12"	12" R.G	15"	15" R.G	18"	24"	24" R.G	27"	30"	30"EQRS	36"	42"	42" R.G	54"	12"	12" R.G	15"	15" R.G	18"	18" R.G	24"	24" R.G	27"	30"	30" R.G	36"	36" R.G	42"	42" R.G	54"	48"	12"	15"	24"	30"	36"	42"	CU YD
146	4-04-INA	4-05-MHA4	5.6	1.79	5.6																																					0.2
147	4-05-MHA4	4-05A-FES	29	0.55					29																																	0
148	4-06A MHA4	4-03A-MHA4	126.2	0.40					126.2																																	0
149	4-08-MHA4	4-05-MHA4	126.1	0.50																			126.1																			0
150	4-06-INA	4-06A MHA4	6	1.67	6																																					0.3
151	4-07-INA	4-08-MHA4	5.6	1.79	5.6																																					0.3
152	4-11-MHA4	4-08-MHA4	126	0.50																	126																					4.1
153	4-09-INA	4-09A-MHA4	6	1.67	6																																					0.2
154	4-09A-MHA4	4-06A MHA4	125.9	0.41			125.9																																			3.4
155	4-10-INA	4-11-MHA4	5.7	1.75	5.7																																					0.3
156	4-12A-MHA4	4-09A-MHA4	127.2	0.40			127.2																																			2.8
157	4-14-MHA4	4-11-MHA4	125.2	0.50			125.2																																			7.1
158	4-13-INA	4-14-MHA4	6.6	1.52	6.6																																					0.3
159	4-12-INA	4-12A-MHA4	6	1.67	6																																					0.3
160	4-15A-MHA4	4-12A-MHA4	101.3	0.40			101.3																																			0
161	4-15-INA	4-15A-MHA4	5.4	1.85	5.4																																					0.2
162	4-16-INB	4-14-MHA4	104.2	0.50			104.2																																			17.2
163	4-19-INB	4-16-INB	127	0.50	127																																					21.8
164	4-18A-MHA4	4-15A-MHA4	124.8	0.40	124.8																																					0
165	4-18-INA	4-18A-MHA4	6	1.67	6																																					0.2
166	4-21A-MHA4	4-18A-MHA4	126	0.51	126																																					0
167	4-21-INA	4-21A-MHA4	6	1.67	6																																					0.2
168	4-22-INA	4-19-INB	127.5	0.50	127.5																																					11.5
169	4-24-INA	4-25-MHA4	40.8	0.98	40.8																																					4.8
170	4-25-MHA4	4-26-FES	15.3	5.62	15.3																																					0
171	5-01-INA	5-02-INB	6.3	0.63	6.3																																					0.2
172	5-02-INB	5-03-FES	27.3	0.44	27.3																																					1.2
173	7-01-INA	7-04-INB	84.2	0.50	84.2																																					9.2
174	7-02-INA	7-03-MHA4	8.3	1.20															8.3																							0.5
175	7-03-MHA4	7-06-MHA5	82.9	0.97															82.9																							0
176	7-04-INB	7-05-INB	70	0.49	70																																					10.4
177	7-05-INB	7-06-MHA5	7.2	1.39															7.2																							0.3
178	7-06-MHA5	7-09-MHA5	126.6	0.81																										126.6												0
179	7-07-INA	7-11-INB	107.7	0.56	107.7																																					14.1
180	7-08-INA	7-09-MHA5	9.2	1.09	9.2																																					0.3
181	7-09-MHA5	7-15-MHA5	106.3	0.80											106.3																											0
182	7-12-INB	7-11-INB	7	1.00	7																																					0.6
183	7-11-INB	7-14-INB	70	0.43			70																																			10.4
184	7-13-INA	7-14-INB	7.5	1.33	7.5																																					0.2
185	7-14-INB	7-15-MHA5	8.5	1.18			8.5																																			0.2
186	7-16-INA	7-12-INB	81.1	0.70	81.1																																					8.8
187	7-15-MHA5	7-18-MHA5	87.3	0.80																										87.3												0
188	7-17-INA	7-18-MHA5	10.1	0.99															10.1																							0.4
189	7-18-MHA5	7-21-MHA5	145.5	0.80																										145.5												0
190	7-19-INA	7-19A-MHA7	50	0.60	50																																					3.2
191	7-20-INA	7-21-MHA5	10.8	0.93	10.8																																					0.3
		TOTAL THIS SHEET			1081.4	0	662.3	0	155.2	0	0	0	0	0	106.3	0	0	0	108.5	0	126	0	126.1	0	0	0	0	0	0	359.4	0	0	0	0	0	0	0	0	0	0	0	135.5

LEGEND

R.G. = RUBBER GASKETED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE 7/5/2012

DRAWN BY SJF

CHECKED BY MED

TUG PROJ. = 31052014
PLOT DATE = 7/5/2012
FILE NAME = p:\civil_dot_dist3\oswego\phase ii\Schedule9.dgn