CONTRACT NO. 66420

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-)IR	KENDALL	514	50
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

PIPE RUN	UPSTREAM STRUCTURE	DOWNSTREAM STRUCTURE	LENGTH	SLOPE	STORM SEWERS, CLASS A, TYPE 1														STORM SEWERS, CLASS A, TYPE 2															S.S. CLASS A, TYPE 3	STORM SEWER (WATER MAIN REQUIREMENTS)						TRENCH BACKFILL
			FEET	%	12"	12" R.G	15"	15" R.G	18"	24"	24" R.G	27"	30"	30"EQRS	36"	42"	42" R.G	54"	12"	12" R.G	15"	15" R.G	18"	18" R.G	24"	24" R.G	27"	30"	30" R.G	36"	36" R.G	42"	42" R.G	54"	48"	12"	15"	24"	30"	36"	42"	CU YD
14-08-MHA5	14-09-MHA5		105.4	0.86																																	105.4				5.9
14-10-INA	14-09-MHA5		8	0.62	8																																				0.1
15-01-INA	15-02-INB		72.7	0.15	72.7																																				3.1
15-02-INB	15-03-MHA4		5	1.00	5																																				0.2
15-03-MHA4	15-04-MHA4		143.7	0.34	143.7																																				12
15-04-MHA4	15-05-MHA5		115.3	0.24			115.3																																		7.1
15-05-MHA5	15-08-MHA5		81	0.30					81																																52
15-06-INA	15-07-INB		41.5	0.36	41.5																																				2.8
15-07-INB	15-08-MHA5		2.9	3.45	2.9																																				0
15-08-MHA5	15-09-FES		260	0.20					260																																166.9
16-01-INA	16-02-MHA4		5.2	1.92	5.2																																				0.1
16-02-MHA4	16-03-MHA5		60.9	5.78	60.9																																				0
16-03-MHA5	16-04-FES		28.3	0.28			28.3																																		0
16-05-INA	16-06-MHA4		5.3	1.89	5.3																																				0.1
16-06-MHA4	16-03-MHA5		53.9	0.24																	53.9																				0
16-07-INA	16-06-MHA4		76.2	0.38	76.2																																				1.7
16-08-FES	16-09-MHA4		97.1	0.14				97.1																																	0
16-09-MHA4	16-11-MHA4		74.7	0.19				74.7																																	0
16-10-INA	16-11-MHA4		10.8	0.93	10.8																																				0.1
16-11-MHA4	16-12-CS6		7	0.43				7																																	0
16-12-CS6	EXISTING		121.9	0.27				121.9																																	0
		TOTAL THIS SHEET		424.2	8	143.6	0	300.7	341	0	0	0	0	0	0	0	0	0	0	0	53.9	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	105.4	0	0	0	252.1
		TOTAL ALL SHEETS		6155	320	1159	103	956	475	235	13	17	122	197	28	43	5	1385	365	2090	0	401	202	1666	246	1182	863	57	2667	278	2073	53	486	108	241	245	144	61	108	685	8124

ROCK EXCAVATION FOR STRUCTURES

STATION	TO STATION	SIDE	CU YD
890+25	892+32	RIGHT	151.0
892+32	902+00	RIGHT	894.7
897+70	897+70	ACROSS	17.7
897+97	898+97	ACROSS	21.0
900+00	900+78	LEFT	13.9
900+47	900+47	ACROSS	29.6
901+97	901+97	ACROSS	48.8
902+00	903+48	RIGHT	299.3
903+48	903+48	ACROSS	8.1
907+00	907+75	RIGHT	15.9
907+00	907+75	LEFT	15.9
907+75	911+53	RIGHT	171.6
907+75	911+10	LEFT	133.4
909+57	909+57	RIGHT	6.0
909+77	909+77	LEFT	1.2
911+10	913+82	LEFT	143.7
911+53	915+58	RIGHT	251.9
911+53	911+53	RIGHT	7.3
913+68	913+68	RIGHT	3.7
913+82	918+81	LEFT	259.2
914+93	914+93	LEFT	1.1
915+58	917+48	RIGHT	125.9
915+58	915+58	RIGHT	5.2
916+27	916+27	LEFT	0.7
917+48	920+91	RIGHT	258.5
917+48	917+48	RIGHT	8.4
917+61	917+61	LEFT	0.5
918+81	918+81	LEFT	1.6
		TOTAL	2896

LEGEND

R.G. = RUBBER GASKETED

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.

DATE 7/5/2012

DRAWN BY SJF

CHECKED BY MED

TUG PROJ. #3385014
PLOT DATE = 7/5/2012
FILE NAME = p:\civil_idot.dgn\3\oswego\phase 1\Schedule1.dgn