

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1)R	KENDALL	514	64
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

**CURB AND GUTTER SCHEDULE**

STATION	TO	STATION	CONCRETE CURB, AND GUTTER, TYPE B LIN. FT.	CONCRETE CURB AND GUTTER, TYPE B-6.12 LIN. FT.	CONCRETE CURB AND GUTTER, TYPE B-6.18 LIN. FT.	CONCRETE CURB AND GUTTER, TYPE B-6.24 LIN. FT.	CLASS S1 CONCRETE (OUTLET) CU. YD.	PROTECTIVE COAT SQ YD	COMMENTS
<b>MINKLER/ORCHARD</b>									
58+06.97	LT.	58+12.06	LT.				0.42	2.2	
58+12.06	LT.	61+47.61	LT.			329.6		109.9	
58+11.57	RT.	61+51.74	RT.			349.6		116.5	
63+70.74	LT.	65+00.00	LT.			129.3		43.1	
64+32.06	RT.	65+00.00	RT.			67.9		22.6	
63+22.38	RT.	63+30.25	RT.			25		8.3	ISLAND
63+31.32	RT.	63+51.38	RT.			20		6.7	ISLAND
65+00.00	LT.	66+67.64	LT.			191.7		63.9	
68+94.94	LT.	71+30.00	LT.			452.5		150.8	
65+00.00	RT.	71+30.00	RT.			639.1		213.0	
<b>MAIN/DOUGLAS</b>									
50+59.66		51+31.08		205.2				45.6	CUL-DE-SAC
101+09.72	LT.	101+64.84	LT.			111.8		37.3	
101+31.61	LT.	103+54.25	LT.			317.1		105.7	
104+54.15	LT.	106+05.95	LT.			152.6		50.9	
101+11.75	RT.	105+93.00	RT.			459		153.0	
<b>FOREST</b>									
46+20.20	LT.	46+73.44	LT.	53.3				11.8	
46+73.44	LT.	49+15.27	LT.			242.9		81.0	
46+20.20	RT.	46+86.01	RT.	65.9				14.6	
46+86.01	RT.	49+18.73	RT.			232.8		77.6	
50+79.75	LT.	51+88.92	LT.			109.6		36.5	
52+60.90	LT.	53+10.00	LT.	50.1				11.1	
50+88.05	RT.	51+59.17	RT.			72.7		24.2	
51+59.17	RT.	53+10.00	RT.	151.9				33.8	

**CURB AND GUTTER SCHEDULE**

STATION	TO	STATION	CONCRETE CURB, AND GUTTER, TYPE B LIN. FT.	CONCRETE CURB AND GUTTER, TYPE B-6.12 LIN. FT.	CONCRETE CURB AND GUTTER, TYPE B-6.18 LIN. FT.	CONCRETE CURB AND GUTTER, TYPE B-6.24 LIN. FT.	CLASS S1 CONCRETE (OUTLET) CU. YD.	PROTECTIVE COAT SQ YD	COMMENTS
<b>PLAINFIELD/WASHINGTON</b>									
189+00	LT.	189+05	LT.				0.42	2.2	
189+05.00	LT.	194+46.00	LT.			596.3		198.8	
194+19.91	LT.	194+80.30	LT.			127.3		42.4	
194+91.17	LT.	198+00.00	LT.			385.8		128.6	
189+00	RT.	189+05	RT.				0.42	2.2	
189+05.00	RT.	194+58.77	RT.			569.5		189.8	
194+78.77	RT.	198+00.00	RT.			335.2		111.7	
191+37.35	LT.	191+53.20	LT.			26		5.8	ENTRANCE
191+77.39	LT.	191+91.12	LT.			23.7		5.3	ENTRANCE
192+87.56	LT.	192+96.83	LT.			19.3		4.3	ENTRANCE
193+20.83	LT.	193+30.92	LT.			18.7		4.2	ENTRANCE
197+12.75	LT.	197+14.94	LT.			40.9		11.4	ENTRANCE
197+61.45	LT.	197+64.14	LT.			39.1		10.9	ENTRANCE
198+00.00	LT.	198+77.87	LT.			78.5		26.2	
198+00.00	RT.	198+67.99	RT.			68		22.7	
199+35.61	LT.	199+48.95	LT.			13.3		4.4	ISLAND
199+61.62	LT.	199+61.88	LT.			12.7		4.2	ISLAND
198+40.46	LT.	198+41.68	LT.	21.0					PARKING LOT
198+41.68	LT.	198+97.62	LT.	56.0					PARKING LOT
198+97.62	LT.	198+99.86	LT.	38.4					PARKING LOT
198+99.86	LT.	199+11.48	LT.	17.3					PARKING LOT
199+11.48	LT.	199+20.76	LT.	9.3					PARKING LOT
199+40.90	RT.	199+48.62	RT.			7.7		2.6	ISLAND
199+61.19	RT.	199+61.33	RT.			11.7		3.9	ISLAND
201+14.37	LT.	207+54.44	LT.			653.8		217.9	
208+04.85	LT.	209+00.08	LT.			94.9		31.6	
200+86.21	RT.	209+00.08	RT.			800.4		266.8	
205+86.08	RT.	205+98.09	RT.			38.9		8.6	ENTRANCE
206+23.02	RT.	206+25.25	RT.			39.5		8.6	ENTRANCE
<b>TOTAL THIS SHEET</b>			142.0	692.5	80	7668.3	1.26	2735.5	
<b>TOTAL ALL SHEETS</b>			142.0	2220.5	80	37037.7	2	12870.4	

**MOUNTABLE CURB AND GUTTER SCHEDULE**

STATION	TO	STATION	CONCRETE CURB AND GUTTER, TYPE M-6.06 LIN. FT.	CONCRETE CURB AND GUTTER, TYPE M-6.06 VARIABLE WIDTH LIN. FT.	PROTECTIVE COAT SQ YD	COMMENTS
<b>MINKLER/ORCHARD</b>						
63+39.75	RT.	63+54.67	RT.	29.9	3.9	ISLAND
<b>PLAINFIELD/WASHINGTON</b>						
199+33.28	LT.	199+52.60	LT.	27.1	3.5	ISLAND
199+37.69	RT.	199+52.46	RT.	22.2	2.886	ISLAND
<b>TOTAL</b>			29.9	49.3	10.3	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE 7/5/2012

DRAWN BY SJF  
 CHECKED BY MED

TUG PROJ: 1305814  
 PLOT DATE: 7/5/2012  
 FILE NAME: I:\PROJECTS\1305814\1305814.dwg  
 PLOTTER: HP DesignJet 5000