

F.A.P. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-D) R	KENDALL	514	72
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

TEMPORARY SIDEWALK SCHEDULE			
LOCATION	STAGE	DESCRIPTION OF WORK	APPROX QTY (SQ FT)
IL 71			
RIGHT OF IL 71 FROM STA. 887+00 TO STA. 910+00	PRE 1	INSTALL TEMPORARY SIDEWALK AT PROPOSED R-O-W PRIOR TO REMOVING ANY EXISTING SIDEWALK. THIS WILL ALSO ALLOW CONSTRUCTION OF PROPOSED SIDEWALK IN STAGE 2 WITHOUT SIDEWALK CLOSURE.	14,500
LEFT SIDE OF IL 71 FROM STA. 897+00 TO STA. 904+00	1	CONSTRUCT ALL PROPOSED SIDEWALK PRIOR TO REMOVAL OF EXISTING SIDEWALK.	
LEFT SIDE OF IL 71 FROM STA. 904+00 TO STA. 917+00	1	INSTALL ALL AS TEMPORARY SIDEWALK PRIOR TO REMOVAL OF EXISTING SIDEWALK.	6,500
LEFT SIDE OF IL 71 FROM STA. 917+00 TO STA. 918+86	1	CONSTRUCT ALL PROPOSED SIDEWALK PRIOR TO REMOVAL OF EXISTING SIDEWALK.	
FOREST AVENUE			
EAST SIDE OF FOREST AVE FROM STA. 49+10 TO STA. 49+34	PRE 1	INSTALL TEMPORARY SIDEWALK	120
EAST SIDE OF FOREST AVE FROM STA. 50+70 TO STA. 52+92	PRE 1	INSTALL TEMPORARY SIDEWALK, MAKE TEMPORARY CROSSING AT IL 71 AND DETOUR PEDESTRIAN TRAFFIC TO EAST SIDE OF ROAD AT PRAIRIEVIEW DR	1,110
PLAINFIELD / WASHINGTON			
NORTH SIDEWALK, EAST SIDE OF WASHINGTON STA. 200+40 TO STA. 209+00	PRE 1	INSTALL TEMPORARY SIDEWALK OUTSIDE TEMPORARY PAVEMENT PRIOR TO REMOVAL OF EXISTING SIDEWALK.	4,300
NORTH - SOUTH SIDEWALKS, WEST SIDE OF PLAINFIELD / WASHINGTON	1	CONSTRUCT ALL PROPOSED SIDEWALK PRIOR TO REMOVAL OF EXISTING SIDEWALK.	
TOTAL			26,530
USE			30,000

NOTE:

THE TEMPORARY SIDEWALK SCHEDULE ABOVE OUTLINES ONE REASONABLE APPROACH TO MAINTAINING PEDESTRIAN TRAFFIC DURING CONSTRUCTION. A NOMINAL QUANTITY OF TEMPORARY SIDEWALK IS INCLUDED IN THE CONTRACT QUANTITIES TO BE USED TO MAINTAIN PEDESTRIAN TRAFFIC ROUTES. SEE THE "MAINTENANCE OF TRAFFIC CONSTRUCTION DETAILS" SHEET FOR ADDITIONAL TEMPORARY SIDEWALK DETAILS.

TEMPORARY STRIPING SCHEDULE (CONTINUED)												
LOCATION	TEMPORARY PAVEMENT MARKING, LINE 4"					TEMPORARY PAVEMENT MARKING, LINE 24"	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS			WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)
	SOLID WHITE (FOOT)	SKIP-DASH WHITE (FOOT)	DOTTED WHITE (FOOT)	SOLID YELLOW (FOOT)	DOUBLE YELLOW (FOOT)		SOLID WHITE (FOOT)	LEFT ARROW (SQ FT)	RIGHT ARROW (SQ FT)			
STAGE 5B												
IL RTE 71												
STA. 787+00 TO STA. 801+00	881	0	0	0	0	0	0	0	0	295	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 53+70 TO STA. 62+59.67	960	0	0	0	960	11	0	0	0	662	0	0
STA. 62+59.67 TO STA. 74+78	1749	0	0	0	1538	11	0	0	0	1118	0	0
STAGE 5B SUBTOTALS	3,590	0	0	0	2,498	22	0.0	0.0	0.0	2,075	0	0
STAGE 5C												
IL RTE 71												
STA. 787+00 TO STA. 801+00	860	0	0	0	0	0	0	0	0	287	0	0
STA. 801+00 TO STA. 815+00	105	0	0	0	0	0	0	0	0	35	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 56+70 TO STA. 62+59.67	210	0	0	0	0	0	0	0	0	70	0	0
STAGE 5C SUBTOTALS	1,175	0	0	0	0	0	0.0	0.0	0.0	392	0	0
STAGE 6												
IL RTE 71												
STA. 780+45 TO STA. 787+00	1810	0	0	1310	0	0	0	0	0	774	0	0
STA. 787+00 TO STA. 801+00	791	0	76	3238	0	67	46.8	15.6	52	1620	0	0
STA. 801+00 TO STA. 818+00	824	0	100	3000	0	0	46.8	15.6	0	1373	0	0
ORCHARD ROAD / MINKLER ROAD												
STA. 56+70 TO STA. 62+59.67	280	0	52	0	1895	34	31.2	0	52	997	0	0
STA. 62+59.67 TO STA. 74+78	1414	0	100	2122	4128	33	15.6	15.6	0	919	0	0
STAGE 6 SUBTOTALS	4,299	0	328	9,670	6,023	134	140.4	46.8	104.0	5,683	0	0
TOTALS (ALL STAGES)	168,053	6,622	4,823	52,173	138,270	2,724	1,934.4	679.8	858.0	122,121	14,219	602
USE			370,141			2,724		3,464		122,121	14,219	602

BIKE PATH STRIPING SCHEDULE	
LOCATION	PAINT PAVEMENT MARKING - LINE 24" (FOOT)
BIKE PATH	
STA. 838+68, RT	6
STA. 842+28, RT	10
STA. 843+60, RT	10
STA. 882+62, RT	10
STA. 883+75, RT	10
STA. 876+97, RT	10
STA. 879+33, RT	10
STA. 881+23, RT	10
STA. 883+52, RT	10
STA. 884+13, RT	10
STA. 889+74, RT	10
STA. 890+30, RT	10
STA. 891+68, RT	10
STA. 892+24, RT	10
STA. 896+69, RT	10
STA. 897+59, RT	10
STA. 909+70, RT	10
STA. 911+09, RT	10
TOTAL	176

SUBSTITUTE TAPE FOR PAINT ON NEW CONCRETE SURFACES AS DIRECTED BY THE ENGINEER. AN ESTIMATED QUANTITY HAS BEEN INCLUDED IN THE SUMMARY OF QUANTITIES FOR TYPE III TAPE.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: NONE		DRAWN BY: _____
DATE: 7/3/2012		

SCHEDULES

ILL PROJ. #S06020
 PLOT DATE = 7/3/2012
 FILE NAME = C:\S06020\CONV\171\SCHED_QT.SHT