

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
311	(1-1R)	KENDALL	514	235
STA. 780+44.91		TO STA. 918+85.88		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

### EROSION CONTROL / LANDSCAPING SCHEDULE

STA TO STA	OFFSET	25000350 SEEDING CLASS 7 (PER STAGE) ACRE	28000250 TEMPORARY EROS CONTR SEEDING (15 TIMES MAX) POUND	28000305 TEMPORARY DITCH CHECKS FOOT	28000400 PERIMETER EROSION BARRIER FOOT	28000500 INLET AND PIPE PROTECTION EACH	28001000 AGGREGATE EROSION CONTROL RR4 TON	28100103 STONE RIPRAP CLASS A2 SQ YD	28100105 STONE RIPRAP CLASS A3 SQ YD	28100107 STONE RIPRAP CLASS A4 SQ YD	28200200 FILTER FABRIC SQ YD	INSTALLATION COMMENTS
<b>IL ROUTE 71</b>												
773+30 - 787+00	LT	0.689	--	150	470	4	--	--	22	--	45	
774+34 - 787+00	RT	0.562	--	134	320	4	--	--	12	--	30	Temp seed Prestage 1 & 2
787+00 - 802+00	LT	0.849	--	--	932	16	--	--	5	56	130	
787+00 - 802+00	RT	1.149	--	88	895	19	--	--	12	--	30	Temp seed Prestage 1 & 2
802+00 - 817+00	LT	0.736	--	--	120	12	--	--	--	--	--	
802+00 - 817+00	RT	0.805	--	23	250	18	--	--	24	--	55	Temp seed Prestage 1 & 2
817+00 - 832+25	LT	1.004	--	12	1,255	22	50	10	--	45	160	Riprap for Sed. Basin & discharge
817+00 - 832+25	RT	0.883	--	52	945	27	50	10	5	20	105	Riprap for Sed. Basin & discharge
832+25 - 846+00	LT	1.569	--	32	425	15	100	20	--	119	295	Riprap for Sed. Basin & discharge
832+25 - 846+00	RT	0.781	--	42	770	27	--	--	--	45	95	Temp seed Prestage 1 & 2
846+00 - 861+50	LT	--	75.3	16	1,160	15	--	--	--	--	--	
846+00 - 861+50	RT	--	158.8	140	1,520	17	--	--	--	--	--	Temp seed Prestage 1 & 2
861+50 - 877+00	LT	--	98.9	8	1,190	27	--	--	--	--	--	
861+50 - 877+00	RT	--	144.0	30	1,295	31	--	--	--	--	--	Temp seed Prestage 1 & 2
877+00 - 891+50	LT	--	45.8	8	1,430	15	--	--	--	--	--	
877+00 - 891+50	RT	--	101.4	--	615	30	--	--	--	--	--	Temp seed Prestage 1 & 2
891+50 - 906+50	LT	--	53.5	--	250	16	--	--	--	--	--	
891+50 - 906+50	RT	--	126.0	--	1,290	25	--	--	--	--	--	Temp seed Prestage 1 & 2
906+50 - 923+00	LT	--	39.9	--	360	15	--	--	14	--	30	Existing 18" outfall VIF riprap
906+50 - 923+00	RT	--	86.2	--	1,270	19	--	--	--	--	--	Temp seed Prestage 1 & 2
<b>ORCHARD / MINKLER ROAD</b>												
54+62 - 71+36	LT	0.834	--	13	530	6	50	10	40	35	175	Riprap for Sed. Basin & discharge
54+62 - 71+36	RT	0.853	--	16	1,150	4	80	20	10	30	170	Riprap for Sed. Basin & discharge and at aggregate ditch check
<b>MAIN STREET / DOUGLAS</b>												
51+00 - 106+06	LT	0.264	--	--	765	3	--	--	25	--	45	Temp seed Stage 1, 1A & B
103+00 - 106+06	RT	0.092	--	--	--	9	--	--	12	--	30	Temp seed Stage 1, 1A & C
<b>FOREST AVENUE</b>												
SEE MAINLINE -	--	--	--	--	--	--	--	--	--	--	--	
<b>PLAINFIELD RD / WASH. ST</b>												
188+00 - 207+45	LT	--	34.9	--	545	17	--	--	25	--	45	Riprap for discharge
188+00 - 207+45	RT	--	29.8	20	300	16	--	--	--	--	--	Temp seed Prestage 1 & 2
<b>PROJECT SUBTOTALS</b>		11.070	994.5	784	20,052	429	330	70	206	350	1,440	
<b>MULTIPLIER 15 TIMES</b>			14917.5									
<b>PROJECT TOTAL</b>		11	14900	785	20,100	430	330	70	210	350	1440	

PLOT DATE = 7/9/2012  
 FILE NAME = F:\GIS-1189\11 71 Design\11\_0605\11\_0605.dwg  
 USER NAME = kdbw



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULES

SCALE: VERT.      DRAWN BY: KD  
 HORIZ.              CHECKED BY: MC  
 DATE: 07/06/2012