

80% FED. / 20% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	CONSTR. CODE	CONSTR. CODE
				ROADWAY	SN	SN
				0004	027-0072	027-0073
				RURAL	ROADWAY 0014	ROADWAY 0014
40600300	AGGREGATE (PRIME COAT)	TON	6	6		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1		
40600525	LEVELING BINDER (HAND METHOD), N50	TON	1	1		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	222	222		
40600990	TEMPORARY RAMP	SO YD	32	32		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	245	245		
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	85	85		
44000100	PAVEMENT REMOVAL	SO YD	405	405		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	42	42		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	1365	1365		
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	2		1	1
50102400	CONCRETE REMOVAL	CU YD	27.4		5.4	22.0
50200100	STRUCTURE EXCAVATION	CU YD	138		70	68
50300225	CONCRETE STRUCTURES	CU YD	75.4		35.1	40.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	577.6		325.3	252.3

FILE NAME *	USER NAME * #USER*	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN -	REVISED -			796	(106 BR-1 & BR-4BR)	FORD	78	4	
#MODELNAME#		CHECKED -	REVISED -			CONTRACT NO. 66980					
		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					