

PIPE UNDERDRAINS - SCHEDULE (3 OF 4)									
LOCATION STATION TO STATION		PIPE UNDERDRAINS 4"						NOTES	
		WB O/S	WB I/S	EB I/S	EB O/S	LT	RT		
FROM	TO	FOOT							
<b>IL ROUTE 94 / 116</b>									
10+00	13+50					350	350	Begin LT & RT Underdrains	
13+50	17+00					350	350		
17+00	20+05					305		End LT Underdrain, Connect to Ramp A RT Underdrain	
17+00	20+45						345	End RT Underdrain, Connect to Ramp D RT Underdrain	
22+05	25+30					325			
22+20	25+22						302		
28+06	31+35						329		
28+14	31+20					306			
32+86	36+00						314	Begin RT Underdrain, Connect to Ramp C RT Underdrain	
33+27	36+00					273		Begin LT Underdrain, Connect to Ramp B RT Underdrain	
36+00	40+00					400	400		
40+00	42+85					285	285	End LT & RT Underdrains	
<b>RAMP A</b>									
0+00	3+00						300	Begin RT Underdrain, Connect to US 34 WB O/S Underdrain	
3+00	6+00						300		
4+60	10+00					540		Begin LT Underdrain	
6+00	9+12						312		
9+12	14+00						488		
10+00	14+00					400			
14+00	18+00					400	400		
18+00	21+47						347	End RT Underdrain, Connect to IL 94 LT Underdrain	
18+00	21+76					376		End LT Underdrain, Connect to IL 94 LT Underdrain	
<b>RAMP B</b>									
0+23	2+00						177	Begin RT Underdrain, Connect to IL 94 LT Underdrain	
0+33	2+00					167		Begin LT Underdrain, Connect to IL 94 LT Underdrain	
2+00	6+00					400	400		
6+00	10+00					400			
6+00	11+00						500		
10+00	11+82					182		End LT Underdrain	
11+00	12+50						150		
12+50	14+00						150		
14+00	15+50						150		
15+50	17+00						150		
17+00	18+50						150		
18+50	20+00						150		
20+00	21+50						150		
21+50	23+00						150		
23+00	24+32						132	End RT Underdrain	
<b>RAMP C</b>									
0+00	3+50						350	Begin RT Underdrain, Connect to US 34 EB O/S Underdrain	
3+50	7+50						300		
6+60	10+70					410		Begin LT Underdrain, Connect to US 34 EB I/S Underdrain	
7+50	10+70						320		
10+70	14+00					330	330		
<b>SUBTOTAL 3</b>		<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>6,199</b>	<b>8,531</b>		

FILE NAME = D468409-SHT-25-28-PIPE UNDERDRAINS.dgn

USER NAME = danw  
 PLOT SCALE = 100.0000' / 1in.  
 PLOT DATE = 11/16/2012

DESIGNED - DBS  
 DRAWN - PSBA  
 CHECKED - CSB  
 DATE - 10/2012

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES  
 US ROUTE 34**

SCALE: N.A. SHEET NO. 27 OF 51 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
313	7-2 ; 6-1	HENDERSON	976	56
CONTRACT NO. 68409			ILLINOIS FED. AID PROJECT	