

SEEDING AND EROSION CONTROL SCHEDULE (1 OF 2)

LOCATION	SEEDING, CLASS 1A	SEEDING, CLASS 2A	SEEDING, CLASS 4A	SEEDING, CLASS 5A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	TEMPORARY EROSION CONTROL SEEDING	EROSION CONTROL BLANKET	HEAVY DUTY EROSION CONTROL BLANKET	MULCH, METHOD 2
	ACRE	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND	SO YD	SO YD	ACRE
US ROUTE 34											
STA 512+00.00 TO STA 528+92.63	0.00	1.81	5.70	5.70	676	676	676	751	13,022	0	7.51
STA 528+92.63 TO STA 555+73.12	0.00	4.22	10.58	10.58	1,332	1,332	1,332	1,480	25,424	0	14.80
STA 555+73.12 TO STA 611+78.78	0.00	7.71	15.37	15.37	2,077	2,077	2,077	2,308	32,356	0	23.08
STA 611+78.78 TO STA 693+89.92	0.00	11.36	23.22	23.22	3,112	3,112	3,112	3,458	42,776	0	34.58
STA 693+89.92 TO STA 721+25.00	0.00	4.08	6.36	6.36	940	940	940	1,044	21,128	0	10.44
STA 721+25.00 TO STA 758+00.00	0.00	4.10	12.16	12.16	1,463	1,463	1,463	1,626	41,355	568	16.26
STA 758+00.00 TO STA 776+84.33	0.00	2.36	7.84	7.84	918	918	918	1,020	27,391	903	10.20
STA 776+84.33 TO STA 803+29.29	0.00	4.08	8.83	8.83	1,162	1,162	1,162	1,291	15,350	0	12.91
STA 803+29.29 TO STA 830+00.00	0.00	3.19	5.66	5.66	797	797	797	885	12,817	0	8.85
IL ROUTE 94 / 116											
STA 5+00.00 TO STA 26+70.22	2.35	0.63	4.27	4.27	653	653	653	725	11,520	0	7.25
STA 26+70.22 TO STA 46+00.00	0.00	1.26	5.50	5.50	608	608	608	676	10,835	0	6.76
RAMP A											
STA 6+50.00 TO STA 19+50.00	0.00	0.70	4.30	4.30	450	450	450	500	6,973	0	5.00
RAMP B											
STA 2+00.00 TO STA 11+50.00	0.00	0.59	3.59	3.59	376	376	376	418	6,307	0	4.18
RAMP C											
STA 7+00.00 TO STA 21+97.59	0.00	0.64	5.03	5.03	510	510	510	567	6,840	0	5.67
RAMP D											
STA 0+23.09 TO STA 11+00.00	0.00	0.52	3.39	3.39	352	352	352	391	6,662	0	3.91
SUBTOTAL 1	2.35	47.25	121.80	121.80	26,388	26,388	26,388	17,140	280,756	1,471	171.40

*MULTIPLY BASE TOTAL BY 39 TO ACCOUNT FOR RESEEDING EVERY TWO WEEKS FOR 2 GROWING SEASONS (MARCH 1 - NOVEMBER 30)

FILE NAME = D468409-SHT-44-45-SEEDING.dgn	USER NAME = danw	DESIGNED - DBS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES US ROUTE 34			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - PSBA	REVISED -		313	7-2 ; 6-1	HENDERSON	976	73	CONTRACT NO. 68409		
		CHECKED - CSB	REVISED -		SCALE: N.A.	SHEET NO. 44 OF 51 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
		DATE - 10/2012	REVISED -									