


- RESTRICTED USE SOILS
- SAND DRAINAGE BLANKET & VERT WICK DRAINS

SAND DRAINAGE BLANKET AND VERTICAL PLASTIC DRAINAGE WICKS: SEE CROSS SECTION FOR ESTIMATED LIMITS. ACTUAL LIMITS WILL BE DETERMINED BY ENGINEER.

- (A) STA. 751+93.96, 19.00' RT. TO STA. 755+62.71, 19.00' RT.
1 - TR BAR TRM T1 SPL TAN
275.0' - SPBGR TY A
1 - TRAF BAR TERM T6
- (B) STA. 752+49.41, 59.00' RT. TO STA. 755+55.66, 59.00' RT.
1 - TR BAR TRM T1 SPL TAN
212.5' - SPBGR TY A
1 - TRAF BAR TERM T6
- (C) STA. 754+85.56, 59.00' LT. TO STA. 755+50.23, 59.00' LT.
1 - TRAF BAR TERM T2
100.0' - SPBGR TY A
1 - TRAF BAR TERM T5
- (D) STA. 755+27.39, 19.00' LT. TO STA. 755+54.56, 19.00' LT.
1 - TRAF BAR TERM T2
1 - TRAF BAR TERM T5
- (E) STA. 758+99.28, 59.00' RT. TO STA. 759+76.45, 59.00' RT.
1 - TRAF BAR TERM T5
25.0' - SPBGR TY A
1 - TRAF BAR TERM T2
- (F) STA. 759+06.86, 19.00' RT. TO STA. 759+34.03, 19.00' RT.
1 - TRAF BAR TERM T5
1 - TRAF BAR TERM T2
- (G) STA. 758+98.18, 19.00' LT. TO STA. 762+66.93, 19.00' LT.
1 - TRAF BAR TERM T6
275.0' - SPBGR TY A
1 - TR BAR TERM T1 SPL TAN
- (H) STA. 758+91.41, 59.00' LT. TO STA. 761+97.66, 59.00' LT.
1 - TRAF BAR TERM T6
212.5' - SPBGR TY A
1 - TR BAR TERM T1 SPL TAN



FILE NAME = D468409-sht-22-pln-US34-21.dgn	USER NAME = zachl	DESIGNED - DBS	REVISED -
		DRAWN - PSBA	REVISED -
		CHECKED - CSB	REVISED -
		DATE - 10/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

ROADWAY PLAN AND PROFILE US ROUTE 34	
SCALE:	SHEET NO. 22 OF 67 SHEETS STA. 752+00.00 TO STA. 764+00.00

F.A.P. RTE. 313	SECTION 7-2 ; 6-1	COUNTY HENDERSON	TOTAL SHEETS 976	SHEET NO. 156
CONTRACT NO. 68409				
ILLINOIS FED. AID PROJECT				