

SUMMARY OF QUANTITIES

LOCATION OF WORK: MCLEAN CO.
 FAP 315 (US 136)
 RURAL TWO LANE
 FUNDING BREAKOUT: 80 % FED / 20 % STATE
 CONSTRUCTION TYPE CODE: 0005

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	15.0
20400800	FURNISHED EXCAVATION	CU YD	1,422.0
21400100	GRADING & SHAPING DITCHES	FOOT	153.0
* 25000210	SEEDING, CLASS 2A	ACRE	4.5
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	405.0
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	405.0
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	405.0
* 25100115	MULCH, METHOD 2	ACRE	3.75
* 25100630	EROSION CONTROL BLANKET	SQ YD	3,371.0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450.0
28000305	TEMPORARY DITCH CHECKS	FOOT	3,030.0
28100107	STONE RIPRAP, CLASS A4	SQ YD	131.0
28100109	STONE RIPRAP, CLASS A5	SQ YD	110.0
28200200	FILTER FABRIC	SQ YD	241.0

* SPECIALTY ITEM

SUMMARY OF QUANTITIES

LOCATION OF WORK: MCLEAN CO.
 FAP 315 (US 136)
 RURAL TWO LANE
 FUNDING BREAKOUT: 80 % FED / 20 % STATE
 CONSTRUCTION TYPE CODE: 0005

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10,798.0
40600300	AGGREGATE (PRIME COAT)	TON	211.0
40600627	LEVELING BINDER (MACHINE METHOD), IL-4.5.FG N50	TON	843.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	159.0
40600990	TEMPORARY RAMP	SQ YD	153.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	7,827.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	466.0
40800030	AGGREGATE (PRIME COAT)	TON	10.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	392.0
42001200	PAVEMENT FABRIC	SQ YD	337.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	78,282.0
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	526.0
44004000	PAVED DITCH REMOVAL	FOOT	153.0
44022041	PARTIAL DEPTH REMOVAL, 6"	SQ YD	43.0