

SCHEDULE OF QUANTITIES

28000305 TEMPORARY DITCH CHECKS

SIDE	STATION	TO	STATION	FOOT	SPACING	# REQ.	WIDTH	FOOT
LT	227+50.00	TO	232+00.00	450.0	50	9	10	90.0
RT	227+50.00	TO	231+00.00	350.0	50	7	10	70.0
LT	252+00.00	TO	255+00.00	300.0	38	8	10	80.0
LT	258+00.00	TO	260+00.00	200.0	50	4	10	40.0
RT	259+00.00	TO	260+00.00	100.0	50	2	10	20.0
RT	264+75.00	TO	267+00.00	225.0	38	6	10	60.0
LT	267+50.00	TO	274+00.00	650.0	30	22	10	220.0
RT	270+50.00	TO	272+50.00	200.0	75	3	10	30.0
LT	280+00.00	TO	291+00.00	1100.0	75	15	10	150.0
RT	283+75.00	TO	291+00.00	725.0	75	10	10	100.0
LT	295+00.00	TO	300+00.00	500.0	75	7	10	70.0
RT	304+00.00	TO	308+00.00	400.0	75	5	10	50.0
LT	304+00.00	TO	308+00.00	400.0	50	8	10	80.0
RT	311+00.00	TO	329+00.00	1800.0	75	24	10	240.0
LT	311+00.00	TO	329+00.00	1800.0	75	24	10	240.0
RT	336+00.00	TO	341+25.00	525.0	75	7	10	70.0
LT	336+00.00	TO	342+00.00	600.0	50	12	10	120.0
RT	348+00.00	TO	355+50.00	750.0	75	10	10	100.0
LT	348+00.00	TO	355+00.00	700.0	50	14	10	140.0
LT	363+00.00	TO	370+00.00	700.0	75	9	10	90.0
LT	375+00.00	TO	380+00.00	500.0	75	7	10	70.0
RT	385+00.00	TO	398+00.00	1300.0	150	9	10	90.0
LT	385+00.00	TO	398+00.00	1300.0	150	9	10	90.0
RT	415+00.00	TO	472+00.00	5700.0	150	38	10	380.0
LT	415+00.00	TO	456+00.00	4100.0	150	27	10	270.0
LT	461+00.00	TO	472+00.00	1100.0	150	7	10	70.0
						TOTAL =		3030.0
						USE =		3030.0

21400100 GRADING AND SHAPING DITCHES

STATION	TO	STATION	SIDE	AREA (SQ. FT.)
289+72.01		291+25.00	LT	153.0
TOTAL =				153.0
USE =				153.0

PATCHING SCHEDULE							
STATION	DIRECTION	LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	44022041	44022051	X4421000
					PARTIAL DEPTH REMOVAL, 6" (SQ YD)	PARTIAL DEPTH REMOVAL, 8 1/2" (SQ YD)	PARTIAL DEPTH PATCHING (TON)
228+02	WB	4.0	13.0	8.25		5.8	2.7
232+35	EB	4.0	13.0	8.25		5.8	2.7
232+35	WB	4.0	13.0	8.25		5.8	2.7
262+43	WB	4.0	13.0	8.25		5.8	2.7
274+39	EB	6.0	13.0	8.25		8.7	4.0
277+16	EB	6.0	13.0	8.25		8.7	4.0
277+34	EB	6.0	13.0	8.25		8.7	4.0
277+34	WB	6.0	13.0	8.25		8.7	4.0
279+55	EB	4.0	13.0	8.25		5.8	2.7
279+55	WB	4.0	13.0	8.25		5.8	2.7
290+75	EB	6.0	13.0	8.25		8.7	4.0
298+29	EB	4.0	13.0	8.25		5.8	2.7
298+29	WB	4.0	13.0	8.25		5.8	2.7
300+78	WB	4.0	13.0	8.25		5.8	2.7
303+90	EB	6.0	13.0	8.25		8.7	4.0
306+30	WB	4.0	13.0	8.25		5.8	2.7
315+40	EB	4.0	13.0	8.25		5.8	2.7
315+40	WB	4.0	13.0	8.25		5.8	2.7
318+15	EB	4.0	13.0	8.25		5.8	2.7
318+15	WB	4.0	13.0	8.25		5.8	2.7
320+00	EB	4.0	13.0	8.25		5.8	2.7
320+00	WB	4.0	13.0	8.25		5.8	2.7
322+75	WB	4.0	13.0	8.25		5.8	2.7
323+90	EB	4.0	13.0	8.25		5.8	2.7
323+90	WB	4.0	13.0	8.25		5.8	2.7
324+17	EB	4.0	13.0	8.25		5.8	2.7
324+17	WB	4.0	13.0	8.25		5.8	2.7
329+50	EB	4.0	13.0	8.25		5.8	2.7
329+50	WB	4.0	13.0	8.25		5.8	2.7
334+82	EB	4.0	13.0	8.25		5.8	2.7
334+82	WB	4.0	13.0	8.25		5.8	2.7
337+00	WB	4.0	13.0	8.25		5.8	2.7
338+30	EB	4.0	13.0	8.25		5.8	2.7
340+10	EB	4.0	13.0	8.25		5.8	2.7
340+10	WB	4.0	13.0	8.25		5.8	2.7
343+50	EB	4.0	13.0	8.25		5.8	2.7
346+25	EB	4.0	13.0	8.25		5.8	2.7
357+00	EB	4.0	13.0	8.25		5.8	2.7
357+00	WB	4.0	13.0	8.25		5.8	2.7
361+22	EB	4.0	13.0	8.25		5.8	2.7
361+22	WB	4.0	13.0	8.25		5.8	2.7
364+87	EB	4.0	13.0	8.25		5.8	2.7
364+87	WB	4.0	13.0	8.25		5.8	2.7
366+50	EB	4.0	13.0	8.25		5.8	2.7
366+80	WB	6.0	13.0	8.25		8.7	4.0

FILE NAME =	USER NAME = ogleb.j	DESIGNED -	REVISED -
ct:\pw\work\p\d0244982\0570783-shd-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 48.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 10/12/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	119RS-4, 18RS & (57-10)RS	MCLEAN	225	20
CONTRACT NO. 70783				
ILLINOIS FED. AID PROJECT				