

SCHEDULE OF QUANTITIES

STATION	DIRECTION	LANE	LENGTH (FOOT)	WIDTH (FOOT)	CLASS B, PATCH AREA				DOWEL BARS 1 1/2" 44201299 (EACH)	SAW CUTS 44213200 (FT.)	TIE BARS 1 1/4" 44213208 (EACH)	PAVEMENT FABRIC 44213100 (SQ. YD.)
					TYPE I 8.0" (SQ. YD.)	TYPE II 8.0" (SQ. YD.)	TYPE III 8.0" (SQ. YD.)	TYPE IV 8.0" (SQ. YD.)				
2035+98	EB	TL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2035+98	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2037+00	EB	DL	8.0	14.0	0.0	12.4	0.0	0.0	24.0	58.0	0.0	0.0
2037+50	WB	DL & TL	6.0	24.0	0.0	0.0	16.0	0.0	44.0	84.0	0.0	16.0
2038+25	EB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2038+75	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2039+00	EB	DL	9.0	14.0	0.0	14.0	0.0	0.0	24.0	60.0	0.0	0.0
2039+00	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2039+15	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2039+85	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2040+00	WB	DL	8.0	14.0	0.0	12.4	0.0	0.0	24.0	58.0	0.0	0.0
2041+50	EB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2041+50	WB	DL	30.0	14.0	0.0	0.0	0.0	46.7	36.0	102.0	30.0	46.7
2042+10	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2042+50	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2043+16	WB	DL & TL	6.0	24.0	0.0	0.0	16.0	0.0	44.0	84.0	0.0	16.0
2043+60	WB	DL & TL	6.0	24.0	0.0	0.0	16.0	0.0	44.0	84.0	0.0	16.0
2044+00	EB	DL	12.0	14.0	0.0	0.0	18.7	0.0	24.0	66.0	0.0	18.7
2044+40	WB	DL & TL	6.0	24.0	0.0	0.0	16.0	0.0	44.0	84.0	0.0	16.0
2044+65	WB	TL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2045+60	EB	DL & TL	6.0	24.0	0.0	0.0	16.0	0.0	44.0	84.0	0.0	16.0
2045+75	WB	TL	6.0	10.0	0.0	6.7	0.0	0.0	16.0	42.0	0.0	0.0
2046+00	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2047+15	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2048+15	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2049+75	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2050+00	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2051+25	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2051+60	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
2052+10	EB	DL	30.0	14.0	0.0	0.0	0.0	46.7	36.0	102.0	30.0	46.7
2052+40	EB	DL & TL	8.0	15.0	0.0	13.3	0.0	0.0	26.0	61.0	0.0	0.0
2052+50	EB	DL & TL	6.0	20.0	0.0	13.3	0.0	0.0	36.0	72.0	0.0	0.0
2053+00	EB	DL & TL	8.0	20.0	0.0	0.0	17.8	0.0	36.0	76.0	0.0	17.8
2053+50	EB	TL	6.0	10.0	0.0	6.7	0.0	0.0	16.0	42.0	0.0	0.0
2053+80	WB	DL	6.0	14.0	0.0	9.3	0.0	0.0	24.0	54.0	0.0	0.0
SUB TOTALS					0.0 (SQ. YD.)	256.2 (SQ. YD.)	116.4 (SQ. YD.)	93.3 (SQ. YD.)	974.0 (EACH)	2185.0 (FT.)	60.0 (EACH)	209.8 (SQ. YD.)

FILE NAME =	USER NAME = oglebj	DESIGNED - ___	REVISED - ___
ci:\pw\work\p\dot\oglebj\d0244982\0570783-sht-schedule.dgn		DRAWN - ___	REVISED - ___
	PLOT SCALE = 40.0000' / in.	CHECKED - ___	REVISED - ___
	PLOT DATE = 10/9/2012	DATE - ___	REVISED - ___

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: _____	SHEET NO. ___ OF ___ SHEETS	STA. _____	TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	119RS-4, 18RS & (57-10)RS	MCLEAN	225	22
CONTRACT NO. 70783				
ILLINOIS FED. AID PROJECT				