


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	STRUCTURAL		
20100500	TREE REMOVAL, ACRES	ACRE	0.5	0.5			
20200100	EARTH EXCAVATION	CU YD	435	435			
20200200	ROCK EXCAVATION	CU YD	50	50			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	50	50			
20400800	FURNISHED EXCAVATION	CU YD	115	115			
20800150	TRENCH BACKFILL	CU YD	47	47			
* 25000200	SEEDING, CLASS 2	ACRE	0.25	0.25			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	22.5	22.5			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	22.5	22.5			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	22.5	22.5			
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.5	0.5			
* 25100115	MULCH METHOD, 2	ACRE	0.25	0.25			
25100630	EROSION CONTROL BLANKET	SQ YD	451	451			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100			

\* SPECIALTY ITEM



USER NAME - Plotted by Roadways?	DESIGNED - SGL	REVISED -
PLOT SCALE - 1/8"=1'-0" / IN.	DRAWN - SGL	REVISED -
PLOT DATE - 10/19/2012	CHECKED - FML	REVISED -
	DATE - 9/2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL ROUTE 96 OVER INLET DITCH  
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 01 OF 06 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
510	120B-3	HANCOCK	38	3
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT			CONTRACT NO. 72B67	