

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				ROADWAY	STRUCTURAL		
				0004	0011		
42000300	PORTLAND CEMENT CONCRETE PAVEMENT 8"	SQ YD	179	179			
42001300	PROTECTIVE COAT	SQ YD	57	57			
44000100	PAVEMENT REMOVAL	SQ YD	83	83			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	301	301			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	76	76			
44000400	GUTTER REMOVAL	FOOT	214	214			
44004250	PAVED SHOULDER REMOVAL	SQ YD	13	13			
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	10	10			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	700	700			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	28	28			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	188	188			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50105220	PIPE CULVERT REMOVAL	FOOT	62	62			
50901760	PIPE HANDRAIL	FOOT	70		70		



USER NAME * Plotted by Roadways?	DESIGNED - SOL	REVISED -
	DRAWN - SOL	REVISED -
PLOT SCALE * 100.0000 / IN.	CHECKED - FML	REVISED -
PLOT DATE * 10/19/2012	DATE - 9/2012	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL ROUTE 96 OVER INLET DITCH  
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 03 OF 06 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
510	120B-3	HANCOCK	38	5
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT			CONTRACT NO. 72B67	