

STRIPING ITEMS-IL 29

LOCATION	PAVEMENT MARKING LINE 6' ' DOTTED (WHITE) (FOOT)	PAVEMENT MARKING LINE 6' ' SOLID (WHITE) (FOOT)	PAVEMENT MARKING LINE 8' ' SOLID (WHITE) (FOOT)	PAVEMENT MARKING LINE 8' ' SOLID (YELLOW) (FOOT)	PAVEMENT MARKING LINE 12' ' SOLID (WHITE) (FOOT)	PAVEMENT MARKING LINE 12' ' SOLID (YELLOW) (FOOT)	PAVEMENT MARKING LETTERS & SYMBOLS "YIELD" (SQFT)	PAVEMENT MARKING LETTERS & SYMBOLS ARROWS (SQFT)	PAVEMENT MARKING REMOVAL (SQFT)
SANGAMON COUNTY									
ILL 29 & TR 205/TANSEY (NBL)	26.53								
ILL 29 & TR 205/TANSEY (SBL)	25.88								
ILL 29 & TR 231/TUXHORN (NBL)	28.01		128.33		48.59				
ILL 29 & TR 231/TUXHORN (SBL)	19.25	8.05	84.74		21.38		12.6		
ILL 29 & TAFT DR (NBL + N MEDIAN)	16.62		98.98	65.58	48.32	32.65			
ILL 29 & TAFT DR (SBL + S MEDIAN)	14.90	18.00	96.38	96.67	24.47	74.76	12.6		
ILL 29 & CAMELOT DR (NBL + N MEDIAN)			112.50	110.39	64.13	87.92			
ILL 29 & CAMELOT DR (SBL)	15.31	9.27	125.69	100.82	42.13	73.89	12.6		
ILL 29 & JOHNS ST (NBL)	16.73	7.55	118.55		17.69		12.6		
ILL 29 & JOHNS ST (SBL)	26.60								
ILL 29 & WALBERTA RD (NBL)									
ILL 29 & WALBERTA RD (SBL)	26.33						12.6		
ILL 29 & TR 412/MAXHEIMER ROAD (NBL)	16.17	8.32	190.31		78.48		12.6	15.6	15.6
ILL 29 & TR 412/MAXHEIMER ROAD (SBL)	16.17	8.24	190.31		68.12		12.6	15.6	15.6
ILL 29 & TR 275/BRANER ROAD (NBL)	22.52	10.63	218.61		90.63		12.6	15.6	15.6
ILL 29 & TR 275/BRANER ROAD (SBL)	22.64	11.17	241.23		99.07		12.6	15.6	15.6
ILL 29 & TR 452/LEACH ROAD (NBL)	17.88	2.73	227.22		87.14		12.6	15.6	15.6
ILL 29 & TR 452/LEACH ROAD (SBL)	18.26		150.16		98.34		12.6	15.6	15.6
CHRISTIAN COUNTY									
ILL 29 & TR 110/VILLA RD/E1700N (NBL)	17.13		207.23		85.09		12.6	15.6	15.6
ILL 29 & TR 110/VILLA RD/E1700N (SBL)	17.13		207.23		85.47		12.6	15.6	15.6
ILL 29 & TR 107/E1900N (NBL)	21.97		194.32		69.09		12.6	31.2	15.6
ILL 29 & TR 107/E1900N (SBL)	22.03		194.09		69.42		12.6	31.2	15.6
ILL 29 & TR 111A/SHARPSBURG RD/E1800N (NBL)	20.55		249.79		105.95		12.6		
ILL 29 & TR 111A/SHARPSBURG RD/E1800N (SBL)	20.95		248.86		100.69		12.6	31.2	31.2
ILL 29 & TR 130A/N1000E (NBL)	17.20		213.80		90.46		12.6	15.6	15.6
ILL 29 & TR 130A/N1000E (SBL)	17.13		212.61		81.90		12.6		
ILL 29 & TR 129B/E1700N (NBL)	19.82		228.11		86.40		12.6		
ILL 29 & TR 129B/E1700N (SBL)	20.95	6.21	228.11		90.19		12.6		
ILL 29 & TR 142/N1100E (NBL)		16.24	61.87		26.73				
ILL 29 & TR 142/N1100E (SBL)	16.82		130.80		52.05		12.6	15.6	15.6
ILL 29 & TR 147A (SBL)		10.99	124.19		65.07			15.6	15.6
TOTAL	541.5	117.4	4,484.0	373.5	1,797.0	269.2	277.2	265.2	234.0

FILE NAME =	USER NAME = sparksgw	DESIGNED - EK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\p\idot\sparksgw\0290765\06721-sht-schedule.dgn	DRAWN - EK	REVISED -											
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED - JM	REVISED -		SCALE: NTS	SHEET	OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 72F21
	PLOT DATE = Oct-17-2012 01:57:10PM	DATE -	REVISED -										