

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LOSEL, 01	LZOEL, 01	LOSEL, 01	LOSEL, 01	LZOEL, 01
				CONSTRUCTION CODE				
				80% FED / 20% STATE NHS-IL 4 ROADWAY	80% FED / 20% STATE STP-IL 97 ROADWAY	80% FED / 10% STATE / 10% CITY NHS-IL 4 TRAFFIC SIGNALS	80% FED / 20% STATE NHS-IL 4 BRIDGE	80% FED / 20% STATE STP-IL 97 BRIDGE
				0005 URBAN	0005 URBAN	0021 URBAN	0014 URBAN	0014 URBAN
44000100	PAVEMENT REMOVAL	SO YD	171	171				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6872	2601	4271			
44000600	SIDEWALK REMOVAL	SO FT	204	204				
44003100	MEDIAN REMOVAL	SO FT	17048	10055	6993			
44004250	PAVED SHOULDER REMOVAL	SO YD	265	265				
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SO YD	65.8	65.8				
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SO YD	16.8	16.8				
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SO YD	28	28				
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	75.6		75.6			
44201299	DOWEL BARS 1 1/2"	EACH	189		189			
44213000	PATCHING REINFORCEMENT	SO YD	345	345				
44213200	SAW CUTS	FOOT	1468	1084.4	383.6			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	910	774	136			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	3002	2471	531			