

PAVEMENT PATCHING SCHEDULE									
FAP 662/67 (IL 4/97) LOCATION	DIMENSIONS (LENGTH X WIDTH) S.B.	CLASS A 8"			CLASS A (SPECIAL) 8"	CLASS B 10"	PATCHING REINFORCMENT (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS (EACH)
		TYPE II (SQ YD)	TYPE III (SQ YD)	TYPE IV (SQ YD)	TYPE III (SQ YD)	TYPE II (SQ YD)			
		5-15 SQ YD	15-25 SQ YD	25+ SQ YD	15-25 SQ YD	5-15 SQ YD			
IL 4 (VETERANS)									
S.B.	6 X 12	8.0					8.0	36.0	
S.B.	12 X 12		16.0				16.0	48	
S.B. (HALF LANE)	40 X 6			26.7			26.7	92.0	
S.B. (HALF LANE)	15 X 6	10.0					10.0	42.0	
S.B. (HALF LANE)	10 X 6	6.7					6.7	32.0	
S.B. (HALF LANE)	8 X 6	5.3					5.3	28.0	
S.B. RT. T.L.	6 X 12	8.0					8.0	36.0	
S.B. RT. T.L.	6 X 12	8.0					8.0	36.0	
S.B. RT. T.L. (HALF LANE)	10 X 6	6.7					6.7	32.0	
S.B. RT. T.L. (HALF LANE)	9 X 6	6.0					6.0	30.0	
S.B. RT. T.L. (HALF LANE)	6 X 6	4.0					4.0	24.0	
NB - STA. 223+43.5 TO 223+58.5	15 X 12				20.0		20.0	54.0	
SB - STA. 223+43.5 TO 223+58.5	15 X 12				20.0		20.0	54.0	
NB - STA. 223+64.5 TO 223+79.5	15 X 12				20.0		20.0	54.0	
SB - STA. 223+64.5 TO 223+79.5	15 X 12				20.0		20.0	54.0	
NB - STA. 237+07.5 TO 237+22.5	15 X 12				20.0		20.0	54.0	
SB - STA. 237+07.5 TO 237+22.5	15 X 12				20.0		20.0	54.0	
NB - STA. 237+07.5 TO 237+22.5	15 X 12				20.0		20.0	54.0	
SB - STA. 237+07.5 TO 237+22.5	15 X 12				20.0		20.0	54.0	
NB - STA. 242+16.5 TO 242+31.5	15 X 12				20.0		20.0	54.0	
SB - STA. 242+16.5 TO 242+31.5	15 X 12				20.0		20.0	54.0	
NB - STA. 242+11.5 TO 242+26.5	15 X 12				20.0		20.0	54.0	
SB - STA. 242+11.5 TO 242+26.5	15 X 12				20.0		20.0	54.0	
IL 97 (JEFFERSON)									
E.B.	6 X 12					8.0		36.0	20.0
E.B.	6 X 12					8.0		36.0	20.0
E.B.	6 X 12					8.0		36.0	20.0
WINCH LANE									
	6 X 12					8.0		36.0	20.0
	6 X 12					8.0		36.0	20.0
	6 X 12					8.0		36.0	20.0
	6 X 12					8.0		36.0	20.0
	6 X 12					8.0		36.0	20.0
	6 X 12					8.0		36.0	20.0
5% ADDED FOR WINTER DETERIORATION		3.1	0.8	1.3		3.6		59.6	9.0
*FINAL LOCATIONS AND DIMENSIONS TO BE DETERMINED IN THE FIELD									
TOTALS		65.8	16.8	28.0	240.0	75.6	345.3	1467.6	189.0

SIDEWALK SCHEDULE							
LOCATION STATION	LENGTH (FT)	WIDTH (FT)	SIDEWALK REMOVAL (SQ FT)	PCC SIDEWALK, 4" (SQ FT)	PCC SIDEWALK, 8" (SQ FT)	DETECTABLE WARNINGS (SQ FT)	CONC CURB TY M (FT)
IL 4 (VETERANS PKWY)							
STA. 10+03.56	RT	7.9	4.0	31.6	31.6	16.0	13.1
STA. 10+03.56	CL	14.1	4.0	56.4	56.4	16.0	25.8
STA. 10+03.56	LT	6.9	4.0	27.6	27.6	16.0	13.9
CIDER MILL RD							
STA. 9+12.00	RT	12.4	4.0	49.6	49.6	8.0	
STA. 10+71.11	RT	9.6	4.0	38.4	38.4	8.0	
TOTAL			203.6	88.0	115.6	64.0	52.8

HOT-MIX ASPHALT BASE COURSE, 12"					
STATION TO STATION FAP 662/67 (IL 4/97)	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	HMA BASE CSE 12" (SQ YD)	SUB-BASE GRAN. MAT. TY A, 6" (TON)
IL 97 (JEFFERSON ST.)					
RIGHT					
STA. 115+81.23 TO STA. 118+21.97	240.74	VARIES	374	373.8	147.3
TOTAL				373.8	147.3