

**SHOULDER SCHEDULE**

LOCATION STATION TO STATION FAP 662/67 (IL 4/97)	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)	HOT-MIX ASPHALT SHOULDERS,			BITUMINOUS MATERIALS (PRIME COAT) (TON)		
					2 1/2" (TON)	2 1/4" (TON)	VARIABLE DEPTH (TON)			
<b>IL 97 (JEFFERSON ST.)</b>										
RIGHT STA. 93+98.37 TO STA. 102+97.60	899.23	4	399.7				50.4	0.15		
RIGHT STA. 102+97.60 TO STA. 103+26.38	28.78	4 TO 10	22.4				3.1	0.01		
RIGHT STA. 103+27.38 TO STA. 104+99.63	172.25	10	191.4				26.8	0.07		
<b>STA. EQ. 104+99.63 BK = 107+95.18 AH</b>										
RIGHT STA. 107+95.18 TO STA. 115+83.24	788.06	10	875.6				122.6	0.33		
RIGHT STA. 115+83.18 TO STA. 118+21.96	238.78	10	265.3	265.3			37.1	0.10		
RIGHT STA. 118+21.96 TO STA. 119+95.75	173.79	VARIES	310.06				43.4	0.12		
LEFT STA. 93+98.99 TO STA. 97+60.83	361.84	4	160.8				22.5	0.06		
LEFT STA. 99+24.61 TO STA. 102+00.01	275.40	2	61.2				8.6	0.02		
LEFT STA. 102+00.01 TO STA. 103+33.46	133.45	2 TO 8	74.1				10.4	0.03		
LEFT STA. 103+33.46 TO STA. 104+99.63	166.17	8	147.7				20.7	0.06		
<b>STA. EQ. 104+99.63 BK = 107+95.18 AH</b>										
LEFT STA. 107+95.18 TO STA. 114+17.51	622.33	8	553.2				77.4	0.21		
LEFT STA. 116+20.86 TO STA. 119+47.32	326.46	10	362.7				50.8	0.14		
LEFT STA. 119+47.32 TO VET STA 222+88.88	197.00	VARIES	108.9				15.3	0.04		
<b>EMPORIA AVE.</b>										
RIGHT STA. 9+75.68 TO STA. 9+03.35	72.33	VARIES	41.2				5.8	0.02		
LEFT STA. 9+75.93 TO STA. 8+76.32	99.61	4	44.3				6.2	0.02		
<b>WINCH RD.</b>										
RIGHT STA. 10+30.22 TO STA. 11+54.61	124.39	VARIES	108.6				15.2	0.04		
LEFT STA. 10+37.34 TO STA. 11+54.61	117.27	VARIES	104.0				14.6	0.04		
*HMA SHOULDERS VARIABLE DEPTH USED 2" FOR A AVE. DEPTH										
				<b>SUB-TOTAL</b>	<b>265.3</b>		<b>480.4</b>	<b>50.4</b>	<b>0.0</b>	<b>1.46</b>
				<b>SUB-TOTAL</b>	<b>265.3</b>		<b>2820.6</b>	<b>50.4</b>	<b>130.9</b>	<b>7.81</b>
				<b>TOTAL</b>	<b>265.3</b>		<b>3001.9</b>			<b>7.81</b>

**LONGITUDINAL JOINT REPAIR**

LOCATION STATION TO STATION FAP 662/67 (IL4/97)	LENGTH (FT)	BIT MAT (PRIME COAT) (TON)
<b>IL 4 (VETERANS PKWY)</b>		
STA. 254+25.00 TO STA. 257+25.00	LT 300.0	0.03
STA. 255+25.00 TO STA. 256+75.00	RT 150.0	0.01
STA. 241+25.00 TO STA. 248+00.00	RT 675.0	0.06
STA. 234+00.00 TO STA. 240+00.00	LT 600.0	0.05
<b>IL 97(JEFFERSON ST)</b>		
STA. 102+97.00 TO STA. 104+99.63	LT 202.6	0.02
<b>STA EQ 104+99.63 BK = 107+95.18 AH</b>		
STA. 107+95.18 TO STA. 114+17.57	LT 622.4	0.05
STA. 109+00.00 TO STA. 123+91.76	LT 1491.8	0.13
STA. 108+14.13 TO STA. 123+75.85	RT 1561.7	0.13
STA. 112+62.68 TO STA. 115+78.20	RT 315.5	0.03
STA. 115+00.00 TO STA. 117+84.00	LT 284.0	0.02
STA. 115+81.67 TO STA. 120+42.49	RT 460.8	0.04
STA. 116+82.39 TO STA. 121+64.80	RT 482.4	0.04
STA. 120+09.73 TO STA. 123+87.48	LT 377.8	0.03
<b>TOTAL</b>	<b>7524.0</b>	<b>0.64</b>

**THERMOPLASTIC PAVEMENT MARKING**

LOCATION STATION TO STATION FAP 662/67 IL 4/ IL 97	LENGTH (FT)	THERMO PLASTIC PAVEMENT MARK - LINE 5" (FT)				THERMO PLAS PAVE MARK TY-B - LINE 12" (FT)
		EDGE LINE		CENTER LINE	SKIP-DASH	
<b>IL 4 (VETERANS PARKWAY)</b>						
<b>SOUTH BOUND</b>						
		WHITE	YELLOW	YELLOW	YELLOW	CHEVRON YELLOW
STA. 216+00.00 TO STA. 224+03.80	803.8	871.5	982.9			
STA. 224+85.00 TO STA. 255+45.30	3,060.3	3156.7	3323.1			
STA. 255+88.10 TO STA. 274+50.00	1,861.9	1768.8	1846.9			
SUB-TOTAL		5797.0	6152.9			
<b>IL 4 (VETERANS PARKWAY)</b>						
<b>NORTH BOUND</b>						
STA. 216+00.00 TO STA. 224+03.80	803.8	663.5	776.8			
STA. 224+85.00 TO STA. 255+45.30	3,060.3	2869.8	3023.0			
STA. 255+88.10 TO STA. 274+50.00	1,861.9	1980.5	2044.6			
SUB-TOTAL		5513.8	5844.4			
<b>IL 97 (JEFFERSON ST.)</b>						
STA. 82+20.00 TO STA. 89+55.00	735.0	1470.0		1470.0		
STA. 89+55.00 TO STA. 94+34.00	479.0	958.0		1916.0		80.00
STA. 94+34.00 TO STA. 98+04.00	370.0	700.0		622.0		
STA. 98+65.00 TO STA. 104+99.18	634.2	1298.0		1268.4	320	
<b>STA. EQ. 104+99.63 BK = 107+95.18 AH</b>						
STA. 107+95.18 TO STA. 115+01.00	705.8	1409.0		1424.0	160	
STA. 115+89.00 TO STA. 120+44.00	455.0	1129.0		997.0		31.00
STA. 121+66.00 TO STA. 123+84.00	218.0	567.0		435.0		
SUB-TOTAL		7531.0	1432.0	6700.4	480.0	111.0

**THERMOPLASTIC PAVEMENT MARKING**

LOCATION STATION TO STATION FAP 662/67 IL 4/ IL 97	LENGTH (FT)	THERMO PLASTIC PAVEMENT MARK - LINE 5" (FT)				THERMO PLAS PAVE MARK TY-B - LINE 12" (FT)
		EDGE LINE		CENTER LINE	SKIP-DASH	
<b>CIDER MILL RD.</b>						
		WHITE	YELLOW	YELLOW	YELLOW	CHEVRON YELLOW
STA. 8+20.70 TO STA. 9+51.83	131.1	337.0		204.0		
STA. 10+48.59 TO STA. 12+22.69	174.1	422.0		286.0		
SUB-TOTAL		759.0		490.0		
<b>EMPORIA AVE</b>						
STA. 10+00.00 TO STA. 8+76.34	123.7	246.0		122.0		
SUB-TOTAL		246.0		122.0		
<b>WINCH RD.</b>						
STA. 10+00.00 TO STA. 11+55.12	155.1	357.0		210.0		
SUB-TOTAL		357.0		210.0		
<b>COLOR SUB-TOTAL</b>		<b>20203.8</b>	<b>13429.3</b>	<b>7522.4</b>	<b>480.0</b>	<b>111.0</b>
<b>TOTAL</b>			<b>41635.5</b>			<b>111.0</b>