

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

90% FED. 10% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	90% FED. 10% STATE						
				0005	0014	0014	0014	0014	0021	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	23622	23622						
48301000	PROTECTIVE COAT	SQ YD	889	765	88	36				
50102400	CONCRETE REMOVAL	CU YD	116.8		29.1	16.7		51.2	19.8	
50104650	SLOPE WALL REMOVAL	SQ YD	8					8		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	134.3		36.3	19.2		57	21.8	
50300300	PROTECTIVE COAT	SQ YD	320		89	36		133	62	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	7690			3120	450	4120		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	21,150		6500	2800		8560	3290	
50800515	BAR SPLICERS	EACH	148		64	16		52	16	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	1152.5		263	325.5		297	267	
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	20201		4562	5202		7948	2489	
58770015	BRIDGE DECK CONCRETE SEALER	SQ FT	32,614		4387	6026	12,157	7654	2390	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	60		3		15	40	2	
60100945	PIPE DRAINS 12"	FOOT	350	350						