

GUARDRAIL SCHEDULE

LOCATION			STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS (FOOT)	TRAFFIC BARRIER TERMINAL, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 6B (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT (EACH)	GUARDRAIL REMOVAL (FOOT)	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE A (FOOT)	REMOVE AND REERECT STEEL PLATE BEAM GUARDRAIL, TYPE B (FOOT)	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 1 (EACH)	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 2 (EACH)	REMOVE AND REERECT TRAFFIC BARRIER TERMINALS, TYPE 6 (EACH)	TRAFFIC BARRIER TERMINAL REMOVAL (EACH)			GUARDRAIL MARKERS, TYPE A (EACH)	TERMINAL MARKER - DIRECT APPLIED (EACH)
GUARDRAIL LOCATION NO	ROADWAY	SIDE											TYPE 1	TYPE 5	TYPE 6		
1	I-255 SB	LT								1							
2A	I-255 NB	RT					112.5					1					
2B	I-255 NB	LT					100.0					1					
3	I-255 SB	LT		1			28.5							1			
4	I-255 NB	RT		1			28.5				1			1			
5	I-255 SB	RT								1							
6	I-255 SB	LT								1							
7	I-255 NB	RT		1			28.5		1284		1						
8	I-255 NB	RT						175.0		1	1						
11	I-255 NB	RT						287.5		1			1				
12	I-255 NB	LT						237.5		1			1				
13	I-255 SB	LT			1		28.5										
14	I-255 NB	RT			1		28.5				1			1			
15	I-255 SB	RT						237.5		1							
16	I-255 SB	LT						287.5		1							
17	I-255 NB	RT						287.5		1							
18	I-255 NB	LT						237.5		1							
19	I-255 SB	LT			1		28.5				1			1			
20	I-255 NB	RT			1		28.5				1			1			
21	I-255 SB	RT						237.5		1							
22	I-255 SB	LT						437.5		1							
25	I-255 SB	LT						325.0		1	1						
28	I-255 NB	RT						425.0		1							
29	I-255 NB	LT						237.5		1							
30	I-255 SB	LT		1			28.5				1			1			
31	I-255 NB	RT		1			28.5				1			1			
32	I-255 SB	RT						237.5		1							
33	I-255 SB	LT						775.0		1							
34	I-255 NB	LT						237.5		1							
35	I-255 SB	RT						237.5		1	1						
36	I-255 SB	LT						287.5		1	1						
37	I-55 Roadway B	LT						187.5		1							
38	I-55 Roadway B	RT						187.5		1							
39	I-55 Roadway B	LT			1		28.5				1			1			
40	I-55 Ramp 1	RT			1		28.5				1			1			
41	I-55 Ramp 1	RT						84.0		1							
42	I-55 Ramp 1	LT						300.0		1							
43	Black Lane	LT	462.5	1		1	575							1	4		1
44	Black Lane	RT	187.5	1		1	325							1	4		1
45	Black Lane	LT	200.0	1		1	300							1	4		1
46	Black Lane	RT	200.0	1		1	750							1	4		1
TOTAL			1050	9	6	4	2264	10028	1284	25	14	20		19	4	16*	4

* NOT A TOTAL QUANTITY

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	SHORT-TERM PAVEMENT MARKING		TEMPORARY PAVEMENT MARKING - LINE 4"			TEMPORARY PAVEMENT MARKING - LINE 8"		WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
	YELLOW (FOOT)	WHITE (FOOT)	SOLID YELLOW (FOOT)	WHITE SKIP DASH (FOOT)	SOLID WHITE (FOOT)	WHITE SKIP DASH (FOOT)	SOLID WHITE (FOOT)	
I-255 NORTHBOUND								
STA 1198+95.00 TO STA 1390+80.00	2398	13740	38372	19642	32280	1932	9260	20603
I-255 SOUTHBOUND								
STA 1240+00.00 TO STA 1435+80.00	3006	15319	39162	20656	35724	2516	11948	22803
COLLINSVILLE ROAD RAMP 7								
STA 100+32.10 TO STA 112+01.90			2350		2410		800	1061
COLLINSVILLE ROAD RAMP 10								
STA 100+00.00 TO STA 101+16.60					234		234	117
55/70 RAMP 1								
STA 113+63.30 TO STA 161+75.50		1448	11552	2416	11112	102	3144	5430
55/70 RAMP 2								
STA 200+00.00 TO STA 225+13.00			4618		4650		410	1682
55/70 RAMP 3								
STA 300+00.00 TO STA 315+54.90			2212		3110		922	1196
55/70 RAMP 4								
STA 400+00.00 TO STA 414+16.20			2456		2834		382	1011
55/70 RAMP 5								
STA 500+00.00 TO STA 517+32.00			3566		3464			1173
55/70 RAMP 6								
STA 600+00.00 TO STA 617+74.70			3654		3550			1201
55/70 ROADWAY A								
STA 700+00.00 TO STA 736+19.00	542	1555	6768	1818	7238		520	3033
55/70 ROADWAY B								
STA 801+89.00 TO STA 867+04.50	689	2688	11492	3074	11744	38	3484	5127
CH 35 RAMP 1								
STA 0+00.00 TO STA 21+43.00			2850		4286		942	1504
CH 35 RAMP 2								
STA 1+54.00 TO STA 17+97.60			2042		2920		956	1147
CH 35 RAMP 3								
STA 0+00.00 TO STA 22+82.00			3610		4528	10	970	1685
CH 35 RAMP 4								
STA 1+39.00 TO STA 28+90.60			4168		6604	130	826	2116
SUBTOTAL	6635	34750	138872	47606	136688	4728	34798	70889
TOTAL	41385		323166		39526		70889	

PAVEMENT MARKING SCHEDULE

LOCATION	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"			PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"		MODIFIED URETHANE PAVEMENT MARKING - LINE 4"			MODIFIED URETHANE PAVEMENT MARKING - LINE 8"		RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	PRISMATIC CURB REFLECTOR (EACH)	PAINT PAVEMENT MARKING CURB (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)
	SOLID YELLOW (FOOT)	WHITE SKIP DASH (FOOT)	SOLID WHITE (FOOT)	WHITE SKIP DASH (FOOT)	WHITE (FOOT)	SOLID YELLOW (FOOT)	WHITE SKIP DASH (FOOT)	SOLID WHITE (FOOT)	WHITE SKIP DASH (FOOT)	WHITE (FOOT)						
I-255 NORTHBOUND																
STA 1198+95.00 TO STA 1390+80.00	15833	8144	13019	833	4082	3353	1677	3121	133	548	1022	106			1128	11673
I-255 SOUTHBOUND																
STA 1240+00.00 TO STA 1435+80.00	15081	7706	13362	1144	5819	4500	2250	4500	114	155	1147	95			1242	12268
COLLINSVILLE ROAD RAMP 7																
STA 100+32.10 TO STA 112+01.90	1175		1205		400								12	91		
COLLINSVILLE ROAD RAMP 10																
STA 100+00.00 TO STA 101+16.60			117		117						3				3	
55/70 RAMP 1																
STA 113+63.30 TO STA 161+75.50	5487	1135	5271	51	1572	289	73	285			188	7			195	613
55/70 RAMP 2																
STA 200+00.00 TO STA 225+13.00	2309		2325		205						40				40	
55/70 RAMP 3																
STA 300+00.00 TO STA 315+54.90	1106		1555		461						36				36	
55/70 RAMP 4																
STA 400+00.00 TO STA 414+16.20	1228		1417		191						21				21	
55/70 RAMP 5																
STA 500+00.00 TO STA 517+32.00	1783		1732								11				11	
55/70 RAMP 6																
STA 600+00.00 TO STA 617+74.70	1827		1775								11				11	
55/70 ROADWAY A																
STA 700+00.00 TO STA 736+19.00	3384	909	3619		260						131				131	
55/70 ROADWAY B																
STA 801+89.00 TO STA 867+04.50	5746	1537	5872	19	1742						210				210	393
CH 35 RAMP 1																
STA 0+00.00 TO STA 21+43.00	1425		2143		471						63				63	
CH 35 RAMP 2																
STA 1+54.00 TO STA 17+97.60	1021		1460		478											
CH 35 RAMP 3																
STA 0+00.00 TO STA 22+82.00	1805		2264	5	485						35				35	
CH 35 RAMP 4																
STA 1+39.00 TO STA 28+90.60	2084		3302	65	413											
SUBTOTAL	61294	19431	60438	2117	16696	8142	4000	7906	247	703	2918	208	12	91	3126	24947
TOTAL	141163			18813		20048		950		2918	208	12	91	3126	24947	

FILE NAME = S:\Projects\1100-2011-255 Study\CAD Sheets\081609-hts-schedule.dgn
 PLOT SCALE = 1/8"=1'-0"
 PLOT DATE = 8/8/2012

USER NAME = Paul
 DESIGNED - ESW
 DRAWN - ESW
 CHECKED - BRM
 DATE - 8-31-11

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES, FAI ROUTE 255

SCALE: SHEET NO. 3 OF 5 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
255	60-(7,8)RS-2	MADISON	261	34
CONTRACT NO. 76A89				
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			