

PATCHING SCHEDULE

LOCATION					CLASS A PATCHES, TYPE II, 10 INCH	CLASS A PATCHES, TYPE III, 10 INCH	CLASS A PATCHES, TYPE IV, 10 INCH	CLASS B PATCHES, TYPE II, 8 INCH	CLASS B PATCHES, TYPE II, 10 INCH	CLASS B PATCHES, TYPE III, 10 INCH	CLASS B PATCHES, TYPE II, 13 INCH	CLASS B PATCHES, TYPE III, 13 INCH	CLASS B PATCHES, TYPE IV, 13 INCH	PATCHING REINFORCEMENT	PAVEMENT FABRIC	SAW CUTS	TIE BARS 3/4"	DOWEL BARS 1 1/2"
STATION	ROADWAY	LANE	LENGTH (FT)	WIDTH (FT)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(FT)	(EACH)	(EACH)
1270+95	I-255 NB	3	6	12	8.0									8.0		61		
1273+73	I-255 NB	3	100	6		66.7								66.7		225	50	
1274+73	I-255 NB	1	6	12	8.0									8.0		61		
1275+00	I-255 NB	3	6	12	8.0									8.0		61		
1275+96	I-255 NB	3	200	6		133.3								133.3		425	100	
1278+98	I-255 NB	4	10	16		17.8								17.8		85		
1289+54	I-255 NB	1	6	12	8.0									8.0		61		
1289+54	I-255 NB	2	6	12	8.0									8.0		61		
1289+54	I-255 NB	3	6	12	8.0									8.0		61		
1305+38	I-255 NB	1	6	12	8.0									8.0		61		
1305+38	I-255 NB	2	6	12	8.0									8.0		61		
1305+38	I-255 NB	3	6	12	8.0									8.0		61		
1347+62	I-255 NB	2	6	12	8.0									8.0		61		
1347+62	I-255 NB	3	100	12		133.3								133.3		249	50	
1349+31	I-255 NB	3	100	12		133.3								133.3		249	50	
1325+70	I-255 NB	3	20	6	13.3									13.3		65		
1246+85	I-255 SB	3	6	12	8.0									8.0		61		
1289+22	I-255 SB	1	10	12	13.3									13.3		69		
1289+22	I-255 SB	2	10	12	13.3									13.3		69		
1289+22	I-255 SB	3	6	12	8.0									8.0		61		
1289+68	I-255 SB	1	6	12	8.0									8.0		61		
1289+68	I-255 SB	2	6	12	8.0									8.0		61		
1289+68	I-255 SB	3	6	12	8.0									8.0		61		
1295+96	I-255 SB	1	6	12	8.0									8.0		61		
1295+96	I-255 SB	2	6	12	8.0									8.0		61		
1295+96	I-255 SB	3	6	12	8.0									8.0		61		
1300+24	I-255 SB	1	6	12	8.0									8.0		61		
1300+24	I-255 SB	2	6	12	8.0									8.0		61		
1300+24	I-255 SB	3	6	12	8.0									8.0		61		
1308+69	I-255 SB	1	6	12	8.0									8.0		61		
1308+69	I-255 SB	2	6	12	8.0									8.0		61		
1308+69	I-255 SB	3	6	12	8.0									8.0		61		
1329+86	I-255 SB	4	100	8		88.9								88.9		233	50	
1330+86	I-255 SB	4	100	16		177.8								177.8		265	50	
1331+92	I-255 SB	3	100	12		133.3								133.3		249	50	
1347+76	I-255 SB	3	20	12		26.7								26.7		89		
1358+32	I-255 SB	4	6	12	8.0									8.0		61		
1367+38	I-255 SB	3	10	12	13.3									13.3		69		
1368+88	I-255 SB	3	50	12		66.7								66.7		149	25	
1370+46	I-255 SB	3	15	6	10.0									10.0		55		
1376+96	I-255 SB	3	12	12		16.0								16.0		73		
1377+66	I-255 SB	3	40	6		26.7								26.7		105	20	
1378+74	I-255 SB	2	8	12	10.7									10.7		65		
1379+44	I-255 SB	3	20	6	13.3									13.3		65		
1381+18	I-255 SB	3	10	12	13.3									13.3		69		
1382+10	I-255 SB	3	12	12		16.0								16.0		73		
1383+10	I-255 SB	3	10	12	13.3									13.3		69		
1383+42	I-255 SB	3	12	12		16.0								16.0		73		
1384+32	I-255 SB	3	10	12	13.3									13.3		69		
1384+72	I-255 SB	3	6	12	8.0									8.0		61		
1387+14	I-255 SB	3	6	12	8.0									8.0		61		
1387+60	I-255 SB	3	6	12	8.0									8.0		61		
100+00	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
101+00	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
101+30	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
101+60	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
101+90	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
102+05	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
102+20	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
102+41	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
102+77	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
103+05	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
103+41	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
103+75	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
104+35	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
104+45	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
104+85	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
105+30	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
107+28	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
107+74	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
107+95	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
110+56	COLLINSVILLE RD RAMP 7	N/A	6	16					10.7							61		28
702+60	I-55/70 ROADWAY A	1	12	12						16.0					16	61		20
703+70	I-55/70 ROADWAY A	1	6	12					8.0							49		20
855+00	I-55/70 ROADWAY B	1	6	12					8.0							49		20
855+00	I-55/70 ROADWAY B	2	6	12					8.0							49		20
856+15	I-55/70 ROADWAY B	1	6	12					8.0							49		20
856+15	I-55/70 ROADWAY B	2	6	12					8.0							49		20
861+75	I-55/70 ROADWAY B	1	6	12					8.0							49		20
861+75	I-55/70 ROADWAY B	2	6	12					8.0							49		20
862+45	I-55/70 ROADWAY B	1	6	12					8.0							49		20
862+45	I-55/70 ROADWAY B	2	6	12					8.0							49		20
SUBTOTAL SHEET 1					351.1	65.8	986.7	0	286.0	16	0	0	0	1403.6	16	6636	445	760

FILE NAME =
S:\Projects\1100-201-255 Study\CAD Sheets\081609-his-schedule.dgn

USER NAME = Paul
PLOT SCALE = 100.0000' / IN.
PLOT DATE = 8/8/2012

DESIGNED - ESW
DRAWN - ESW
CHECKED - BRM
DATE - 8-31-11

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES, FAI ROUTE 255

SCALE: SHEET NO. 4 OF 5 SHEETS STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
255	60-(7,8)RS-2	MADISON	261	35
CONTRACT NO. 76A89				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				