



Patch No.	Patch Depth	Station	Length (ft)	Width (ft)	Quantity (sq. yd.)
1	Partial	1305+43.6	6	4	2.67
2	Partial	1304+99.6	3	2	0.67
3	Partial	1304+87.6	4	3	1.33
4	Partial	1304+05.92	2	2	0.44
5	Partial	1303+39.6	2	2	0.44
6	Partial	1303+30.6	9	4	4.00
7	Partial	1303+30.6	3	3	1.00
8	Partial	1303+30.6	2	2	0.44
9	Partial	1303+22.92	3	2	0.67
10	Partial	1303+16.6	3	3	1.00
11	Partial	1303+04.6	9	5	5.00
12	Partial	1302+95.6	2	2	0.44
13	Partial	1302+66.92	5	3	1.67

DECK PLAN VIEW

NOTE:
 Apply Concrete sealer per Article 587 of the Standard Specifications to top and inside vertical faces of the parapets, end posts, and wing walls. Sealer shall not be applied to concrete surfaces that are to receive water proofing membrane.
 See Note 2, sheet 5 of 16.

LEGEND

	Deck Slab Repair Partial Depth
	Concrete Removal (See concrete removal Sheet)

BILL OF MATERIAL

Item	Unit	Total
Deck Slab Repair - (Partial Depth)	Sq. Yd.	21
Deck Slab Repair - (Full Depth Type I)	Sq. Yd.	2
Concrete Sealer	Sq. Ft.	2789

FILE NAME : 06R9253-76A89-08-Deck_Patching_plan_08.dwg

DESIGNED - WAE	X	DESIGNED - WAE	X
CHECKED - FAS	X	CHECKED - FAS	X
DRAWN - DMG	X	DRAWN - DMG	X
CHECKED - SLZ	X	CHECKED - SLZ	X

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

DECK PATCHING PLAN SOUTHBOUND
 STRUCTURE NO. 060-0253
 SHEET NO. 8 OF 16 SHEETS

F.A.I. RTE. 255	SECTION 60-(7.8) RS-2	COUNTY MADISON	TOTAL SHEETS 261	SHEET NO. 235
ILLINOIS FED. AID PROJECT			CONTRACT NO. 76A89	

