

SUMMARY OF QUANTITIES

100% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004	0014	0014
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8852	8852		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1537.5	1537.5		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3071	3071		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	775	775		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	762.5	762.5		
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1	
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	1	1	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8852	8852		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10	10		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	6	6	
* 78200430	GUARDRAIL MARKERS, TYPE C	EACH	12	6	6	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2951	2951		

* SPECIALTY ITEM

FILE NAME =	USER NAME = chollandeska	DESIGNED -	REVISED -
ci:\p\work\pvidot\chollandeska\0292402	0876F54-ah-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE = 11/2/2012	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE	SHEET 3	OF 3	SHEETS	STA.	TO STA.	F.A.P. RTE. 789	SECTION 125-1HB-1	COUNTY MADISON	TOTAL SHEETS 29	SHEET NO. 5
CONTRACT NO. 76F54								[ILLINOIS] FED. AID PROJECT		

12